Amended Plan

PERMIT

MILL HILL CHILDRENS CENTRE

Existing railings to be relocated to bottom of slope and painted.

Existing raked sections of fencing to be removed

Existing paving to be retained

Existing gate to be relocated and painted

Entrance

New steps to childrens centre

Retaining wall to be removed.

PLAYGROUND

New double gates to match existing hoop top railings.

Existing area of hardstanding to be broken out. Level change to be graded out and grassed

Brick retaining wall with wall mounted entrance sign; details to be agreed

New hedge planting

Existing paving to be retained

LP

Existing fencing to be retained

New steps to lower playground

Pedestrian clearway to be marked

Existing parking bays to be remarked

Bespoke 'entrance feature'

Existing walls and steps to be removed

CAR PARK

Free standing directional sign to be relocated

MILL ROAD

Existing hedgerow to be retained

Existing vehicular kerb to be retained

0 1 2 5

NORTH

AMENDED/ADDITIONAL PLAN
RECEIVED
0 9 JUL 2010
DIRECTOR OF ENVIRONMENT
HAMPSHIRE COUNTY COUNCIL

Key

EXISTING

- TREES TO BE RETAINED
- EXISTING VEGETATION TO BE RETAINED
- EXISTING EXTENTS OF HARDSTANDING / EDGING TO BE REMOVED
- EXISTING TARMAC SURFACING TO BE RETAINED
- LP EXISTING STREET LIGHT TO BE RETAINED

PROPOSED

- DENSE BITUMEN MACADAM PAVING WITH PCC EDGING AS SPECIFIED
- MARSHALLS 'CONSERVATION' CONCRETE PAVING SLABS 'Silver grey' 450x450x50mm LAID STACK BOND AS SPECIFIED
- COUDUROY HAZARD WARNING PAVING 450x450x50mm LAID STACK BOND AS SPECIFIED
- MARSHALLS 'CONSERVATION' STEP UNITS 'Silver grey' WITH BLACK DEMARKATION STRIPS 400x1000mm and150mm HIGH LAID AS SPECIFIED
- 1.0M HIGH METAL HOOP TOP VERTICAL BAR RAILINGS TO MATCH EXISTING AS SPECIFIED
- 0.8M HIGH KNEE RAIL WITH TIMBER UPRIGHTS AND METAL RAIL AS SPECIFIED
- RENDERED AND PAINTED RETAINING WALL TO HEIGHT SHOWN
- 900mm HIGH FIXED TIMBER BOLLARDS AS SPECIFIED
- GALVANISED METAL CYCLE HOOPS WITH SUBMERGED FIXINGS AS SPECIFIED
- SEMI MATURE TREE PLANTING
- MULTISTEM TREE PLANTING
- AMENITY SHRUB PLANTING
- HEDGEROW PLANTING
- AMENITY GRASS

Rev:	Date:	Amendment:	Name:	Checked:
C	08.07.10	Add trees to boundary	DR	NJ
B	22.06.10	For Tender	DR	NJ
A	24.05.10	For Planning	DR	NJ

Drawing Based Upon: Mill Hill Survey

Status: For Planning

Notes: Contractors are not to scale from this drawing. All dimensions to be checked on site and any discrepancies, ambiguities and/or omissions between this drawing and information given elsewhere must be reported to this office.
If in doubt, ask.

RPS
Lakesbury House Hillingbury Road Chandlers Ford Hampshire SO53 5SS
T 023 80810440 F 023 80810449 E rpsas@rpsgroup.com W www.rpsgroup.com

Client: Hampshire County Council

Project: Mill Hill Children's Centre
Landscape Improvements

Title: Proposed Landscape Master Plan

Date: 05/10 Scale: 1:200 Paper Size: A3

Drawn: DR Checked: NJ Job Ref: JSL 1759

Drawing Number: 100 Rev: C

Crown Copyright. All rights reserved. 2009 License number 100048482. Drawing Ref: P:\1700 SERIES\JSL1759 - HCC MILLHILL\TECH\ACAD\CURRENT\1759_100_MILL HILL_MASTER.DWG Plotted Date: 7/9/2010 9:46 AM