



Notes:

Structures adjacent to the works area are shown indicatively in grey.

Areas highlighted in red on the demolition elevation are to be removed. To include the removal of:

- Corrugated asbestos roof and supporting timber structure
- All rainwater goods
- Windows and doors
- Non-listed dwarf wall
- All internal mechanical and electrical items will be removed and isolated/capped off as necessary

The remaining Grade II Listed wall will be stripped of paint and undergo sympathetic, like for like mortar repairs. The original internal doors will be replaced with hardwood timber alternatives in like for like colours (shown in yellow on proposed).

A				

Rev	Description	Date	By	Chkd
-----	-------------	------	----	------

HCC Property Services,
Three Ministers House,
76 High Street, Winchester SO23 8UL
tel: (01962) 847801

HCC
Property Services

PROJECT NAME
Staunton Farm

SHEET NAME
South Elevation
Existing, Demolition and Proposed

SCALE 1:100 @ A3	DRAWN LC	CHKD SG	APRV --
----------------------------	--------------------	-------------------	-------------------

DRAWING No. P14474-HCC-03	version A
-------------------------------------	---------------------

code description