

- IN-20
- Door Undercuts
- Minimum 7600mm2 undercuts beneath all internal doors to allow through ventilation
 - Typically, 10mm gap required between the finished floor level and the bottom of the door
 - Remove door leaf, trim from the bottom and making good where required

MTIP MID TERM
IMPROVEMENT PLAN

- MTIP-2
1
- Insulate the
Solid Floor
- 4.5mm Acousticork T66 Underlay & feathered screed

RM RENEWABLE
MEASURES TO NET
ZERO

- RM-30
- Renewable
Ready Measures
- Install insulated ducting for cabling and pipework; flow and return
 - Separate spur from the fuse board to be supplied to proposed ASHP location
 - Existing roof structure to be inspected by suitably qualified professional to determine its capacity for the weight of future PV

PROPOSED

A3

Scales

Constructive Thinking Studio
Liverpool Science Park IC 1
131 Mount Pleasant
L3 5TF

www.constructivethinking.co.uk
+44 (0) 151 705 5433
bim@constructivethinking.co.uk

Safety Health and Environmental
Information

In addition to the hazard/risks normally associated with the types of work detailed on this drawing take note of the below. It is assumed that all works on this drawing will be carried out by a competent contractor working, where appropriate, to an appropriate method statement.

This document and its design content is copyright ©. It shall be read in conjunction with all other associated project information including models, specifications, schedules and related consultants documents. Do not scale from documents. All dimensions to be checked on site. Immediately report any discrepancies, errors or omissions on this document to the Originator. If in doubt ASK.

Demolition/Adapation Risks

Risk of fragile render, existing cladding and rainwater goods collapsing. Contractor to ensure operatives wear PPE and carry out works carefully. For Further information see Risk Register.

Construction Risks

Risk of injury to operatives through working from height, tripping hazards, etc. Care to be taken while working on site and appropriate PPE to be worn. For further information see Risk Register.

Maintenance/Cleaning Risks

Cleaning windows from height. Appropriate equipment to be used. PPE to be worn. For Further information see Risk Register.

Revision	Date	By	Check
	08/08/2025	WJ	LFS

Client TGP

Project TGP Portsmouth

Status Stage Approval Subject to Building Control - A1 -

Drawings

File 17 Chaucer Close_(AC28)

Measures II

8 Hemsley Walk,
PO8 8JW

Drawing Number

7083 -CTS-000- 08 -D-A-4718

Revision

01