IN-14	New dMEV to be located in kitchen and bathroom	- Where existing extract fans are already present, remove and replace with new dMEV fans; New dMEV fans mount type to match existing i.e. ceiling or wall mount - Where no extract fan is present in any bathroom or kitchen, form/core drill new opening to external air - Refer to ventilation strategy for minimum extract rates - Install to manufacturers specification, install with switched spur to employers requirements

MTIP MID TERM IMPROVEMENT PLAN

MTIP-21	Insulate the Solid Floor	- 4.5mm Acousticork T66 Underlay & feathered screed

RM RENEWABLE MEASURES TO NET ZERO

RM-30	Renewable Ready Measures	- Install insulated ducting for cabling and pipework; flow and return - Separate spur from the fuse board to be supplied to proposed ASHP location - Existing roof structure to be inspected by suitably qualified professional to determine its capacity for the weight of future PV

PROPOSED

A3 Scales

Constructive Thinking Studio
Liverpool Science Park IC 1
131 Mount Pleasant
L3 5TF

www.constructivethinking.co.uk
+44 (0) 151 705 3433
bim@constructivethinking.co.uk

CONSTRUCTIVE THINKING

Safety Health and Environmental Information

In addition to the hazard/risks normally associated with the types of work detailed on this drawing take note of the below. It is assumed that all works on this drawing will be carried out by a competent contractor working, where appropriate, to an appropriate method statement.

This document and its design content is copyright ©. It shall be read in conjunction with all other associated project information including models, specifications, schedules and related consultants documents. Do not scale from documents. All dimensions to be checked on site. Immediately report any discrepancies, errors or omissions on this document to the Originator. If in doubt ASK.

Demolition/Adapation Risks

Risk of fragile render, existing cladding and rainwater goods collapsing. Contractor to ensure operatives wear PPE and carry out works carefully. For Further information see Risk Register.

Construction Risks

Risk of injury to operatives through working from height, tripping hazards, etc. Care to be taken while working on site and appropriate PPE to be worn. For further information see Risk Register.

Maintenance/Cleaning Risks

Cleaning windows from height. Appropritate equipment to be used. PPE to be worn. For Further information see Risk Register.

Revision	Date	By	Check
	21/03/2025		

Client **TGP**

Project **TGP- Portsmouth**

Status **Stage Approval Subject to Building Control - A1 - LFS**

Drawings

File 24 Passingham Walk_(AC28)

Measures II

24 Passingham Walk PO8 8JH

Drawing Number
7083 -CTS- 03 - 24 - L-A-4417

Revision
P06