

EX EXTERNAL
WORKS

EX-10	External Wall to be Insulated and Reinforced	<div>- External Wall to achieve 0.3W/m^2K as per Part L Requirements</div> <div>- Existing Wall to be Reinforced as per Architect's and Structural Engineer's Details</div> <div>- Refer to Architect's Details, Structural Engineer's Details and Calculations, and Manufacturer's Specifications</div>
EX-12	New Cavity Wall Insulation (CWI)	<div>- Integrity of any existing Cavity Wall Insulation to be inspected. If damp is present, extract, dry and replace with resin bead insulation.</div> <div>- Installed as per manufacturer´s spec.</div> <div>- System to be CIGA certified</div>
EX-13	New Windows	<div>- New Windows to achieve U-value of 1.20 W/m2K</div> <div>- All windows to meet FENSA and PAS24 compliance standards</div> <div>- Windows to have trickle vents installed except in wet rooms where dMEV is present</div> <div>-Cavity closers to be inspected</div>
EX-20	New External Doors	<div>-Composite Front Doors to achieve U-value of 1.20 W/m2K</div> <div>- Installed as per manufacturer's technical spec, sealed with expanding foam tape</div> <div>- Internal reveals to be made good, cavity closers to be inspected</div> <div>- Part L doors to be in accordance with manufacturers spec and employers requirements</div>
EX-40	Pitched Roof/ Loft Insulation	<div>- Top up Mineral Wool Quilt Loft Insulation to 400mm, refer to CTS Specification</div> <div>- Ventilation to be ensured with proprietary vent trays if required</div> <div>- Loft Insulation to be rolled into the eaves, ensuring continuous thermal envelope, refer to CTS details</div> <div>- Install new insulated loft hatch as per manufacturer´s specifications</div> <div>- Skeilings to be insulated as per CTS Detail Pack</div> <div>- Inspect existing fascia, soffit and rainwater goods for degradation and replace where neccessary</div>
EX-41-1	Roof Ventilation	<div>- New breathable membrane, battens, tiles, and dry ridge system to be fitted in accordance with manufacturer's details and specification. Client to instruct on material finish. Inspections required to confirm structural integrity of existing roof structure prior to roof replacement.</div>
EX-43	Eaves/Verge Extension	<div>- Eaves/Verges to be Extended where required; Min 40mm overhang from finish face of EWI System</div> <div>- Refer to CTS Detail Pack</div>
EX-46	Roof Tile Vents (if no replacement)	<div>- Existing Roof ventilation strategy to be confirmed for compliance, if breather membrane is present disregard below;</div> <div>- Minimum 2 vent tiles per roofscape, e.g. a hip roof would be 6 tile vents</div> <div>- Vent tiles to be installed as close to eaves as possible and above new insulation height</div> <div>- Vent tiles position to be coordinated to allow provision for potential PV in the future</div>
EX-50	Structural Panel	<div>- Structherm Structural Panel above DPC, unless alternative thickness indicated, installed as per Constructive Thinking Studio (CTS) Detail Pack and Structherm specification and details</div> <div>installed as per manufacturer's technical spec.</div>
EX-60	External Fixtures	<div>-New External Lights</div> <div>-New External Canopy soffit to be installed as per manufacturer's details</div>

IN INTERNAL
WORKS

IN-11	Monitoring Sensors	To be installed as per CTS specifications
-------	--------------------	---

PROPOSED

A3

Scales

Constructive Thinking Studio

Liverpool Science Park IC 1

131 Mount Pleasant

L3 5TF

www.constructivethinking.co.uk

+44 (0) 151 705 3433

bim@constructivethinking.co.uk

Safety Health and Environmental Information

In addition to the hazard/risks normally associated with the types of work detailed on this drawing take note of the below. It is assumed that all works on this drawing will be carried out by a competent contractor working, where appropriate, to an appropriate method statement.

This document and its design content is copyright ©. It shall be read in conjunction with all other associated project information including models, specifications, schedules and related consultants documents. Do not scale from documents. All dimensions to be checked on site. Immediately report any discrepancies, errors or omissions on this document to the Originator. If in doubt ASK.

Demolition/Adaption Risks

Risk of fragile render, existing cladding and rainwater goods collapsing. Contractor to ensure operatives wear PPE and carry out works carefully. For Further information see Risk Register.

Construction Risks

Risk of injury to operatives through working from height, tripping hazards, etc. Care to be taken while working on site and appropriate PPE to be worn. For further information see Risk Register.

Maintenance/Cleaning Risks

Cleaning windows from height. Appropriate equipment to be used. PPE to be worn. For Further information see Risk Register.

Revision	Date	By	Check
	08/08/2025	WJ	LFS

Client

TGP

Project

TGP Portsmouth

Status

Stage Approval Subject to Building Control - A1 -

Drawings

File

17 Chaucer Close_(AC28)

Measures

6 Passingham Walk, PO8 8JH

Drawing Number

7083 -CTS- 20 -000.06 -L-A-4617

Revision

01