



Creek View
Selsmore Road
Hayling Island
PO11 9JZ

Dear 

Many thanks for allowing  to provide you with this quotation for your project at your home. I've outlined below the main allowances and our schedule of works are included within the price.

Please see below a description of works included in your quotation:

- ☐ Remove excessive decorative stones from driveway.
- ☐ Install golden edgings to full perimeter.
- ☐ Create front bow-mouth.
- ☐ Extend driveway approximately 30m² and create an additional pathway to side access gate.
- ☐ Set in edgings to match driveway so path has the same aesthetical look.
- ☐ Top up drive to a minimum depth of 100mm of type one limestone aggregate.
- ☐ Compress with a vibrating roller.
- ☐ Once this has been completed will lay a 40mm topcoat stone covering and compress with roller.
- ☐ Once this has been laid in, this drive will be as equal as a solid surface driveway. It will also look aesthetically pleasing.

