



CCTV REPORT FOR: 28 DAMASK GARDENS
WATERLOOVILLE
PO7 8QZ

CONTENTS: SITE LAYOUT
CCTV SURVEY DETAILS
FOUNDATION RECORD
INVESTIGATION SUMMARY
RECOMMENDATIONS
PHOTOGRAPHS
LABORATORY TESTING RESULTS
ROOT IDENTIFICATION
LIMITATION OF REPORT



Client: 360Globalnet
Regus House
Herald Way
Pegasus Business Park
Castle Donington
DE74 2TZ


Insured: Mrs. Hayley Psaila
Reference: LIV-SN-23-006703 Ins Ref: 800-16-008022

1st Site Visit: 25-May-23
1st Report Date: 28-Jun-23

2nd Site Visit: 21-Aug-23
2nd Report Date: 31-Aug-23

Site Crew: AJE

Date: 21-Aug-23



(This plan is not to be scaled and is provided to illustrate general layout only)

General Comments:

Note: Runs shown in red have been adopted by the local water authority.

Key :
 □ = Storm Gully
 ○ = Storm Pipe
 ⊠ = Foul Gully
 ● = W/C or Soil Pipe
 □ = Inspection Chamber
 ⊙ = Rodding Eye
 —————> = Surveyed pipe indicating flow
 - - - - -> = Unsurveyed pipe
 ⊕ = Exploratory Hole (hand dug pit and/or hand auger)
 - - - - - = Boundary line
 = Hedges & Shrubs
 = Trees & bushes
 = Area of damage

Address: 28 DAMASK GARDENS, WATERLOOVILLE, PO7 8QZ

Site Crew: AJE Date: 21-Aug-23

RUN: 1 Pipe Dia. (mm): 100 System: Storm Water Made of: Plastic
From: RWP1 Inv (m): - Downstream To: MH2 Inv (m): -


Metres	Faults / Defects	Remarks
0.00		At RWP1
7.30	No Visible Defects	At connection to unknown run
		Past area of concern
		End of survey

Defects shown in **RED** relate to runs adopted by the Local Water Authority

Address: 28 DAMASK GARDENS, WATERLOOVILLE, PO7 8QZ

Drainage
 Repair Company
FOUNDATION RECORD

Location: Rear Left Corner of Conservatory	T/H No. 1
Ground Surface: Dry	Weather: Dry
Date: 25-May-23	



Depth (m)	Soil Descriptions (NB: Field crew description only)	Test Type	Depth (m)	
			From	To
G.L.				
0.40	Soft/firm brown CLAY with rare medium gravel (inc. brick) & roots	V(n) 34	0.400	
1.00	Soft/firm brown CLAY with rare medium gravel & roots	V(n) 52	0.500	
1.50	Soft/firm light grey/brown CLAY with rare medium gravel & rootlets	V(n) 70	1.000	
2.00	Firm/stiff grey/brown CLAY with rare medium gravel & rootlets	V(n) 88	1.500	
3.00	Firm/stiff grey/brown CLAY with rare medium gravel	V(n) 126	2.000	
3.80	End of Borehole	V(n) 140+	2.500	
		V(n) 140+	3.000	
		V(n) 140+	3.500	
	Photograph			
				

General Comments :

Key: Mac=Macintosh Probe, V(n)=Natural Shear Vane, P.P. = Pocket Penetrometer

Address: 28 DAMASK GARDENS, WATERLOOVILLE, PO7 8QZ

EXECUTIVE SUMMARY

Brief:	The Drainage Repair Company Ltd were commissioned to undertake a CCTV survey / inspection of the drainage at the property.
Specific Area of Interest:	Accessible drainage at the rear of the property.
System Access:	Inspection chamber in conservatory, RWP1.
Visual Survey:	N/A
Water Pressure Test:	Pass - no leak on water supply detected during acoustic testing.

SUMMARY OF FINDINGS

Defects requiring repair:	See Recommendations
Is any damaged section shared:	See Recommendations
No. of properties sharing:	N/A
Age of property / system:	Unknown
Cause of damage:	N/A

GENERAL SUMMARY

The results of the CCTV / inspection survey to the underground drainage system at the above address are as follows:

Run 1 - Storm - Private:

Pipework runs from RWP1 downstream off the property boundary and connects to an unknown run and 7.3m before running into a chamber (MH2) set into the tarmac parking area.

No visible pipework defects.

RWP2:

The down pipe is located at the rear right corner of the conservatory. It serves the conservatory only and discharges onto the ground against the boundary fence.

MH1:

We carried out high pressure water jetting from MH1 to attempt to clear the build up of grease/fat prior to carrying out a CCTV survey. We jetted the pipework upstream and downstream but we were not able to clear the debris from the pipework.

Tracing the pipework downstream we located a chamber (MH3) set in the grass verge to the left of the neighbouring property. When we lifted the cover to this we found that this was also holding water backing up from pipework further downstream. We attempted to jet from the chamber but were still not able to clear the debris and water.

Unfortunately the high levels of water and debris in the shared pipework prevented a CCTV survey.

RECOMMENDATIONS


We would recommend returning the system to a watertight condition by repairing the defects as follows:

Run 1:


No recommendations are required.

MH3 / Shared Pipework:


There are high levels of debris and standing water in the shared pipework serving MH3. As this pipework is believed to be the responsibility of the local water authority we recommend that they are contacted so that they may clear the blockages from the pipework.



RWP1 access



RWP1 reinstated



MH2 in tarmac parking area



MH2 in tarmac parking area



MH3 in grass verge



MH3 in grass verge




MH3 blocked downstream




MH3



MH1 jetting in progress



MH1 unable to clear




T/H1



T/H2

Drainage
 Repair Company
LABORATORY TESTING RESULTS

Depth T (m)	Depth B (m)	1 - Rear LHC of conservatory Brief Soil Description	Plasticity (BS 5930)	Volume Change M.PI (BRE 240)
0.4	0.5	Soft/firm brown CLAY with rare medium gravel (inc. brick) & roots	High CH	36% Medium
0.5	1	Soft/firm brown CLAY with rare medium gravel & roots	High CH	38% Medium
1	1.5	Soft/firm light grey/brown CLAY with rare medium gravel & rootlets	High CH	41% High
1.5	2	Firm/stiff grey/brown CLAY with rare medium gravel & rootlets	V. high CV	47% High
2	2.5	Firm/stiff grey/brown CLAY with rare medium gravel & rootlets	V. high CV	47% High
2.5	3	Firm/stiff grey/brown CLAY with rare medium gravel & rootlets	V. high CV	48% High
3	3.5	Firm/stiff grey/brown CLAY with rare medium gravel	V. high CV	48% High
3.5	3.8	Firm/stiff grey/brown CLAY with rare medium gravel	V. high CV	47% High



Key:

MC = Natural Moisture Content (%)

E.MC = Equivalent Moisture Content (%) = $MC \times 100 / 425\%$

M.PI = Modified Plasticity Index (%) = $PI \times 425\% / 100$

425% = Material passing the 425µm sieve (%) + (N = Natural or S = Sieved)

Notes: All samples received as Disturbed unless noted below in the comments.

Samples prepared in accordance to BS1377:Part 1:1990 Section 7 & described in general accordance with BS5930:1999.

Samples tested in accordance to BS1377:Part 2:1990 Section 3.2, 4.4 & 5.

Comments:

PL = Plastic Limit (%)

PI = Plasticity Index (%) = $LL - PL$


LL = Liquid Limit (%)

LL x 0.4 = 40% of the LL (%)

NP = Non Plastic

Drainage
 Repair Company
LABORATORY TESTING RESULTS

Depth T (m)	Depth B (m)	2 - R/H side of property	Plasticity (BS 5930)	Volume Change	
		Brief Soil Description		M.PI	(BRE 240)
1.7	2	Soft brown CLAY with rare medium gravel	High CH	44%	High
2	2.2	Soft brown CLAY with rare medium gravel	V. high CV	47%	High



Opinions and interpretations expressed in the chart above are outside the scope of UKAS accreditation.

Key:
MC = Natural Moisture Content (%)
E.MC = Equivalent Moisture Content (%) = $MC \times 100 / 425\%$
M.PI = Modified Plasticity Index (%) = $PI \times 425\% / 100$
425% = Material passing the 425µm sieve (%) + (N = Natural or S = Sieved)
Notes: All samples received as Disturbed unless noted below in the comments.
 Samples prepared in accordance to BS1377:Part 1:1990 Section 7 & described in general accordance with BS5930:1999.
 Samples tested in accordance to BS1377:Part 2:1990 Section 3.2, 4.4 & 5.
Comments:

PL = Plastic Limit (%)
PI = Plasticity Index (%) = $LL - PL$
LL = Liquid Limit (%)
LL x 0.4 = 40% of the LL (%)
NP = Non Plastic



Root identification
Vegetation surveys
Tree/Building investigations
Plant taxonomy

Richardson's Botanical Identifications

The Drainage Repair Company
Suite 15, Leatherline House
71 Narrow Lane
AYLESTONE
Leicester LE2 8NA

Dr Ian B K Richardson
BSc, MSc, PhD, MRSB, FLS
James Richardson
BSc (Hons. Biology)

Enterprise House
49-51 Whiteknights Road
Reading
RG6 7BB

Tel: (0118) 986 9552 (Direct line)
E-mail: richardsons@botanical.net
Web: www.botanical.net

27/06/2023

Your ref: -

Our ref: 87/0710

Dear Sirs

28 Damask Gardens, Waterlooville PO7 8QZ

The samples you sent in relation to the above on 25/05/2023 have been examined. Their structures were referable as follows:

TP/BH1, 0.4-1.4m		
18 no.	Examined root: QUERCUS (Oak).	Alive, recently*.
4 no.	All pieces of BARK only - not enough material for identification.	
10 no.	Unfortunately all with insufficient cells for identification.	
TP/BH1, 1.4-2.4m		
20 no.	Examined root: QUERCUS (Oak).	Alive, recently*.
3 no.	All pieces of BARK only - not enough material for identification.	
20 no.	Unfortunately all with insufficient cells for identification.	
TP/BH1, 2.4-3.4m		
6 no.	Examined root: could also be QUERCUS (Oak). This was a very IMMATURE sample.	Alive, recently*.

Click here for more information: [QUERCUS](#)

I trust this is of help. Please call us if you have any queries; our Invoice is enclosed.

Yours faithfully,

Dr Ian B K Richardson

* Based mainly on the Iodine test for starch. Starch is present in some cells of a living woody root, but is more or less rapidly broken down by soil micro-organisms on death of the root, sometimes before decay is evident. This result need not reflect the state of the parent tree.

** Try out our web site on www.botanical.net **

Identified with no information on vegetation, on or off site.

Report commissioned by



Address: 28 DAMASK GARDENS, WATERLOOVILLE, PO7 8QZ

We were commissioned to carry out an inspection of the accessible areas of the drainage to the property, identifying any major defects and recommending any repair works that may be necessary. It should be appreciated that the exact layout of the system cannot be confirmed without the exposure of inaccessible branches and connections etc.

The lack of any significant defects within the main drainage line should not be regarded as a guarantee of water tightness. Defects may be encountered upon exposure of inaccessible branches and gullies etc.

The contents of this report are strictly confined to comments concerning those terms outlined above. It is not a structural survey and must not be construed as such.

The views expressed in this report are based entirely upon a visual examination of the drainage, supported by information obtained from a CCTV inspection / water pressure test.