

Tree Protection Measures

Once a Root Protection Area (RPA) has been established, protective fencing is to be erected prior to the commencement of all works on site, and retained in place through construction.

Within the protective fencing there is to be:

- No mechanical digging or scraping once initial ground cover has been removed and the barrier erected.
- No storage of plant, equipment, or materials.
- No vehicular or plant access.
- No fire lighting.
- No handling, discharge, or spillage of any chemical substance, including cement washings.
- No action likely to cause localised water-logging
- No change in ground levels.

