

CCTV REPORT FOR: 28 DAMASK GARDENS
WATERLOOVILLE
PO7 8QZ

CONTENTS: SITE LAYOUT
FOUNDATION RECORD
INVESTIGATION SUMMARY
RECOMMENDATIONS
QUOTATION
PHOTOGRAPHS
LABORATORY TESTING RESULTS
ROOT IDENTIFICATION
LIMITATION OF REPORT



Site Visit: 25-May-23
Report Date: 28-Jun-23




Drainage
Repair Company

SITE LAYOUT

Site Crew: AJE

Date: 25-May-23



(This plan is not to be scaled and is provided to illustrate general layout only)

General Comments:


Note: Runs shown in red have been adopted by the local water authority.

Key :
 = Storm Gully = Storm Pipe = Foul Gully = W/C or Soil Pipe = Inspection Chamber
 = Rodding Eye = Surveyed pipe indicating flow = Unsurveyed pipe
 = Exploratory Hole (hand dug pit and/or hand auger) = Boundary line
 = Hedges & Shrubs = Trees & bushes = Area of damage

Address: 28 DAMASK GARDENS, WATERLOOVILLE, PO7 8QZ

Drainage
 Repair Company
FOUNDATION RECORD

Location: Rear Left Corner of Conservatory	T/H No. 1
Ground Surface: Dry	Weather: Dry
Date: 25-May-23	



Depth (m)	Soil Descriptions (NB: Field crew description only)	Test Type	Depth (m)	
			From	To
G.L.				
0.40	Soft/firm brown CLAY with rare medium gravel (inc. brick) & roots	V(n) 34	0.400	
1.00	Soft/firm brown CLAY with rare medium gravel & roots	V(n) 52	0.500	
1.50	Soft/firm light grey/brown CLAY with rare medium gravel & rootlets	V(n) 70	1.000	
2.00	Firm/stiff grey/brown CLAY with rare medium gravel & rootlets	V(n) 88	1.500	
3.00	Firm/stiff grey/brown CLAY with rare medium gravel	V(n) 126	2.000	
3.80	End of Borehole	V(n) 140+	2.500	
		V(n) 140+	3.000	
		V(n) 140+	3.500	
<div style="text-align: center;"> Photograph  </div>				

General Comments :

Key: Mac=Macintosh Probe, V(n)=Natural Shear Vane, P.P. = Pocket Penetrometer

Address: 28 DAMASK GARDENS, WATERLOOVILLE, PO7 8QZ

EXECUTIVE SUMMARY

Brief:	The Drainage Repair Company Ltd were commissioned to undertake a CCTV survey / inspection of the drainage at the property.
Specific Area of Interest:	Accessible drainage at the rear of the property.
System Access:	Inspection chamber in conservatory.
Visual Survey:	N/A
Water Pressure Test:	Pass - no leak on water supply detected during acoustic testing.

SUMMARY OF FINDINGS

MH1:

We identified an inspection chamber beneath an access panel in the floor of the conservatory to the rear of the house. When we accessed this we found the pipework to be approximately 1.0m deep and holding high levels of grease/fat and washing machine residue.

We attempted rodding the clear the debris but this was not successful.

RWP1:

The down pipe is located at the rear right corner of the main house in a narrow gap between the conservatory and the boundary fence. The end panel of the fence is screwed in place and we could not lift this out to gain access to attempt a survey.

RWP2:

The down pipe is located at the rear right corner of the conservatory. It serves the conservatory only and discharges onto the ground against the boundary fence.



RECOMMENDATIONS & QUOTATION

RECOMMENDATIONS

Further Investigation:

Return to site and carry out high pressure water jetting as required before performing a CCTV survey of the drainage connected to MH1, reporting further on the condition and destination of all pipework.

Carry out small access excavation at RWP1 and cut into the pipework below ground. Perform a CCTV survey of the drainage downstream, reporting further on the condition and destination of the pipework.

Should the pipework be found to discharge to a soakaway then perform a flow test to determine whether this is functioning adequately.

Enabling Work:

We will require the first fence panel at the rear right corner of the main house to be removed to allow us access to RWP1. In addition the conservatory area will need to be free of personal items to allow is clear access to MH1.


QUOTATION

Further Investigation:

- Carry out high pressure water jetting from MH1
- Internal surface protections as required
- Carry out small access excavation at RWP1
- Cut into pipework below ground
- Perform CCTV survey
- Carry out flow test if discharge from RWP1 is to soakaway
- Make good access cut to pipework
- Further report on condition and destination of surveyed pipework
- Backfill excavation, reinstate surface, remove spoil from site



MH1 access panel




MH1



RWP1



RWP2




T/H1



T/H2

Drainage
 Repair Company
LABORATORY TESTING RESULTS

Depth T (m)	Depth B (m)	1 - Rear LHC of conservatory Brief Soil Description	Plasticity (BS 5930)	Volume Change M.PI (BRE 240)
0.4	0.5	Soft/firm brown CLAY with rare medium gravel (inc. brick) & roots	High CH	36% Medium
0.5	1	Soft/firm brown CLAY with rare medium gravel & roots	High CH	38% Medium
1	1.5	Soft/firm light grey/brown CLAY with rare medium gravel & rootlets	High CH	41% High
1.5	2	Firm/stiff grey/brown CLAY with rare medium gravel & rootlets	V. high CV	47% High
2	2.5	Firm/stiff grey/brown CLAY with rare medium gravel & rootlets	V. high CV	47% High
2.5	3	Firm/stiff grey/brown CLAY with rare medium gravel & rootlets	V. high CV	48% High
3	3.5	Firm/stiff grey/brown CLAY with rare medium gravel	V. high CV	48% High
3.5	3.8	Firm/stiff grey/brown CLAY with rare medium gravel	V. high CV	47% High



Key:

MC = Natural Moisture Content (%)

E.MC = Equivalent Moisture Content (%) = $MC \times 100 / 425\%$

M.PI = Modified Plasticity Index (%) = $PI \times 425\% / 100$

425% = Material passing the 425µm sieve (%) + (N = Natural or S = Sieved)

Notes: All samples received as Disturbed unless noted below in the comments.

Samples prepared in accordance to BS1377:Part 1:1990 Section 7 & described in general accordance with BS5930:1999.

Samples tested in accordance to BS1377:Part 2:1990 Section 3.2, 4.4 & 5.

Comments:

PL = Plastic Limit (%)

PI = Plasticity Index (%) = $LL - PL$


LL = Liquid Limit (%)

LL x 0.4 = 40% of the LL (%)

NP = Non Plastic

Drainage
 Repair Company
LABORATORY TESTING RESULTS

Depth T (m)	Depth B (m)	2 - R/H side of property	Plasticity (BS 5930)	Volume Change	
		Brief Soil Description		M.PI	(BRE 240)
1.7	2	Soft brown CLAY with rare medium gravel	High CH	44%	High
2	2.2	Soft brown CLAY with rare medium gravel	V. high CV	47%	High



Opinions and interpretations expressed in the chart above are outside the scope of UKAS accreditation.

Key:

MC = Natural Moisture Content (%)

E.MC = Equivalent Moisture Content (%) = $MC \times 100 / 425\%$

M.PI = Modified Plasticity Index (%) = $PI \times 425\% / 100$

425% = Material passing the 425µm sieve (%) + (N = Natural or S = Sieved)

Notes: All samples received as Disturbed unless noted below in the comments.

Samples prepared in accordance to BS1377:Part 1:1990 Section 7 & described in general accordance with BS5930:1999.

Samples tested in accordance to BS1377:Part 2:1990 Section 3.2, 4.4 & 5.

Comments:

PL = Plastic Limit (%)

PI = Plasticity Index (%) = $LL - PL$

LL = Liquid Limit (%)

LL x 0.4 = 40% of the LL (%)

NP = Non Plastic



Root identification
Vegetation surveys
Tree/Building investigations
Plant taxonomy

Richardson's Botanical Identifications

The Drainage Repair Company
Suite 15, Leatherline House
71 Narrow Lane
AYLESTONE
Leicester LE2 8NA

Dr Ian B K Richardson
BSc, MSc, PhD, MRSB, FLS
James Richardson
BSc (Hons. Biology)

Enterprise House
49-51 Whiteknights Road
Reading
RG6 7BB

Tel: (0118) 986 9552 *(Direct line)*
E-mail: richardsons@botanical.net
Web: www.botanical.net

27/06/2023

Your ref: -

Our ref: 87/0710

Dear Sirs

28 Damask Gardens, Waterlooville PO7 8QZ

The samples you sent in relation to the above on 25/05/2023 have been examined. Their structures were referable as follows:

TP/BH1, 0.4-1.4m		
18 no.	Examined root: QUERCUS (Oak).	Alive, recently*.
4 no.	All pieces of BARK only - not enough material for identification.	
10 no.	Unfortunately all with insufficient cells for identification.	
TP/BH1, 1.4-2.4m		
20 no.	Examined root: QUERCUS (Oak).	Alive, recently*.
3 no.	All pieces of BARK only - not enough material for identification.	
20 no.	Unfortunately all with insufficient cells for identification.	
TP/BH1, 2.4-3.4m		
6 no.	Examined root: could also be QUERCUS (Oak). This was a very IMMATURE sample.	Alive, recently*.

Click here for more information: [QUERCUS](#)

I trust this is of help. Please call us if you have any queries; our Invoice is enclosed.

Yours faithfully

Dr Ian B K Richardson

* Based mainly on the Iodine test for starch. Starch is present in some cells of a living woody root, but is more or less rapidly broken down by soil micro-organisms on death of the root, sometimes before decay is evident. This result need not reflect the state of the parent tree.

** Try out our web site on www.botanical.net **

Identified with no information on vegetation, on or off site.

Report commissioned by



Address: **28 DAMASK GARDENS, WATERLOOVILLE, PO7 8QZ**

We were commissioned to carry out an inspection of the accessible areas of the drainage to the property, identifying any major defects and recommending any repair works that may be necessary. It should be appreciated that the exact layout of the system cannot be confirmed without the exposure of inaccessible branches and connections etc.

The lack of any significant defects within the main drainage line should not be regarded as a guarantee of water tightness. Defects may be encountered upon exposure of inaccessible branches and gullies etc.

The contents of this report are strictly confined to comments concerning those terms outlined above. It is not a structural survey and must not be construed as such.

The views expressed in this report are based entirely upon a visual examination of the drainage, supported by information obtained from a CCTV inspection / water pressure test.