

GUY LAWSON Building Ltd

Building & Renovation
Property Maintenance & Landscaping

35 Myrtle Ave, Porchester, Hants PO16 9JS
Tel: 023 92 376613 • Mobile: 07977 783025

2-4-17

Estimate for Helen Taylor, 8 Langstone High St, Havant.

Front of house - Replace 2 tile listings.

Rake out and re-point approx. $1m^2$ of masonry.

Rake out and re-point around ground floor window

Side of house - Put up scaffolding.

Repair and decorate top window

Rake out and re-point approx $6m^2$ of masonry

Repoint at union of tile listing with masonry.

Back of house - Rake out and re-point approx. $1m^2$ of masonry.

Generally - make other small repairs that become apparent within time restraints.

Remove all waste from site.

All pointing to be carried out using moderately hydraulic lime as supplied by Linetec Ltd.

I suggest natural colour.

HAVANT BOROUGH
COUNCIL

10 APR 2017

RECEIVED

*