

CLIENT NAME		CONTACT NUMBER		QUOTATION DATE		JOB NUMBER	
Jenna Dewhurst						J23238	
SITE ADDRESS				INSPECTED BY		Matt Godwin	
103 West Street Havant PO9 1LE				SITE PLAN ATTACHED			No
				COMMENCEMENT DATE		TBA	
TPO / CONSERVATION AREA?				yes	No	Consent Given?	
Titchfield Tree Services to Apply				yes	No	COMMENTS	
JOB DESCRIPTION							
TREE NUMBER (price ex. VAT @20%)	SPECIES/ location	WORK REQUIRED					
T6	Failed Willow south of Lake.	Remove from Lake. With the use of Mewp Rigging and dinky All arisings removed from site.					
T1	Lime ///goad.wink.quit	Remove basle growth sever ivy to expose unions at 3m Remove major deadwood greater than 25mm in diameter Whilst carried out deadwood inspect the unions at 10m					
T2	Mature Lime ///school.adjust.faded	Remove basle growth sever ivy Remove to 1m from ground level Remove major deadwood greater than 25mm in diameter Whilst carried out deadwood inspect the unions and attachment points from lapse pollard Remove regrowth on 2 x lowest southern laterals back to previous points to prevent encroachment onto neighbouring properties maximum live pruning wounds not to exceed 100mm					
T3	Mature Lime ///orders.fishery.hardly	Remove basle growth sever ivy Remove to primary fork at 2.5m from ground level Remove major deadwood greater than 25mm in diameter Whilst carried out deadwood inspect the unions and attachment points from lapse pollard . Concerns of decay within the union at 2.5m on Eastern side;					

		however, occlusion is occurring The lowest southern primary lateral shows a vertical legend on the tension side extending 2m from stem Concerns of the strength of holding wood on Southern lateral at 5m from main stem Lower branches are encroaching onto neighbouring property. Reduce southern primary stem by up to 2m from branch tips or to nearest suitable live pruning points keeping live pruning wounds to a maximum of 75mm Remove large dead branch over neighbouring property lift southern side to 6m from ground level
T4	Mature Lime ///lows.shunts.goes	Remove basal growth sever ivy Remove to expose primary fork at 3.5m Remove major deadwood greater than 25mm in diameter Whilst carried out deadwood inspect the unions and attachment points from lapse pollard
T5	Mature Lime ///clip.fires.vows	Remove basal growth sever ivy Remove to 1m from ground level Remove major deadwood greater than 25mm in diameter Whilst carried out deadwood inspect the unions and attachment points from lapse pollard paying particular attention to the union on Southern side at 6m from ground level -legion on tension side but with good reaction growth on the compression side Large cavity on the Eastern side at 3.5m from ground level, showing good habitat value . Assess cavity Whilst present with ecologist. Remove regrowth from lowest southern lateral back to secondary branch to revert encroaching on neighbouring property.
A site specific risk assessment will be undertaken before the commencement of works, this will encompass Working At Height assessments, site hazards and environmental considerations.		