

Borehole No.: WS2

Site Name: Emsworth Primary School, Victoria Road, Emsworth, Hampshire

Job No.: LW24121

Start Date: 28/05/2013

End Date: 28/05/2013

Standpipe Installation	Samples and Testing					Strata		
	Sample Type	Depths		Vane/ Pen Test N Value	DPSH Profile Blows/100mm 5 15 25	Legend	Depth / Reduced Level	Strata Descriptions
		From (m)	To (m)					
							6.00	Very stiff blue grey silty CLAY. (London Clay Formation) no sample recovery below 5.0m depth.
								End of Borehole

Remarks:

Excavation Method: Dynamic Sampler

Borehole Diameter: Various

Made By: DC

Trial Pit No.: TP1

Site Name: Emsworth Primary School, Victoria Road, Emsworth, Hampshire

Job No.: LW24121

Start Date: 28/05/2013

End Date: 28/05/2013

Samples and Testing				Strata		
Sample Type	Depths		Vane/ Pen Test N Value	Legend	Depth / Reduced Level	Strata Descriptions
	From (m)	To (m)				
					0.00	Ground Level
					0.10	Asphalt.
					0.20	MADE GROUND: Dark brown sandy fine to coarse gravel of crystalline rock.
J T	0.40				0.70	MADE GROUND: Orange brown clayey angular fine to coarse gravel of brick and clay pipe.
J T	0.80					
D	0.90					
V	1.00		125		1.00	Stiff orange brown and grey mottled slightly gravelly silty CLAY. Gravel is fine to medium flint and ironstone. (River Terrace Deposits)
						End of Pit

Remarks:

Groundwater noted beneath foundation at 0.75m depth, rising to 0.6m.

Trial pit stable on completion.

Excavation Method: Hand Dug

Dimensions:

Made By: DC

Trial Pit No.: TP2

Site Name: Emsworth Primary School, Victoria Road, Emsworth, Hampshire

Job No.: LW24121

Start Date: 28/05/2013

End Date: 28/05/2013

Samples and Testing				Strata		
Sample Type	Depths		Vane/ Pen Test N Value	Legend	Depth / Reduced Level	Strata Descriptions
	From (m)	To (m)				
					0.00	Ground Level
					0.10	Asphalt.
					0.20	MADE GROUND: Pink brown sandy fine to coarse gravel of crystalline rock.
J T	0.30				0.55	MADE GROUND: Orange brown slightly gravelly silty clay with roots (up to 5mm diameter). Gravel is fine to coarse flint, brick, glass and plastic.
J T D V	0.60		120		0.70	Stiff orange brown and grey mottled slightly gravelly silty CLAY. Gravel is fine to medium ironstone and flint. (River Terrace Deposits)
						End of Pit

Remarks:
 Trial pit dry and stable on completion.

Excavation Method: Hand Dug

Dimensions:

Made By: DC

ASHDOWN SITE INVESTIGATION LTD


Dynamic Probe Record

SITE Emsworth Primary School, Victoria Road, Emsworth, Hampshire

Report Ref.

LW24121

Test Location Reference			WS1	
Depth (mblgl)	Blows (per 100mm)	Average Penetration per Blow (m)	Unit Point Resistance (MPa)	Dynamic Point Resistance (MPa)
0.10				
0.20	3	0.03	5.66	5.51
0.30	3	0.03	5.66	5.43
0.40	3	0.03	5.66	5.36
0.50	2	0.05	3.77	3.53
0.60	0.3	0.33	0.57	0.52
0.70	0.3	0.33	0.57	0.52
0.80	0.3	0.33	0.57	0.51
0.90	0.5	0.20	0.94	0.84
1.00	0.5	0.20	0.94	0.83
1.10	1	0.10	1.89	1.64
1.20	1	0.10	1.89	1.62
1.30	1	0.10	1.89	1.60
1.40	3	0.03	5.66	4.74
1.50	3	0.03	5.66	4.69
1.60	2	0.05	3.77	3.09
1.70	3	0.03	5.66	4.58
1.80	2	0.05	3.77	3.02
1.90	2	0.05	3.77	2.99
2.00	3	0.03	5.66	4.43
2.10	3	0.03	5.66	4.38
2.20	3	0.03	5.66	4.34
2.30	3	0.03	5.66	4.29
2.40	4	0.03	7.54	5.66
2.50	4	0.03	7.54	5.61
2.60	3	0.03	5.66	4.16
2.70	4	0.03	7.54	5.49
2.80	4	0.03	7.54	5.44
2.90	3	0.03	5.66	4.04
3.00	4	0.03	7.54	5.33
3.10	4	0.03	7.54	5.28
3.20	4	0.03	7.54	5.23
3.30	3	0.03	5.66	3.89
3.40	4	0.03	7.54	5.13
3.50	6	0.02	11.32	7.63
3.60	6	0.02	11.32	7.55
3.70	6	0.02	11.32	7.49
3.80	5	0.02	9.43	6.18
3.90	5	0.02	9.43	6.13
4.00	5	0.02	9.43	6.07
4.10	4	0.03	7.54	4.81
4.20	4	0.03	7.54	4.77
4.30	7	0.01	13.20	8.28
4.40	24	0.00	45.27	28.14
4.50	9	0.01	16.98	10.46
4.60	5	0.02	9.43	5.76
4.70	5	0.02	9.43	5.72
4.80	5	0.02	9.43	5.67
4.90	4	0.03	7.54	4.50
5.00	5	0.02	9.43	5.57



Notes:


Hammer Mass	63.5 kg
Fall Height	0.76 m
Cone Area	0.0019 m ²
E _{theor}	473 J
Energy Ratio	0.757
Anvil Mass	0 kg
Rod Mass	8.79 kg/m

ASHDOWN SITE INVESTIGATION LTD

Dynamic Probe Record

SITE Emsworth Primary School, Victoria Road, Emsworth, Hampshire Report Ref. LW24121

Test Location Reference			WS1	
Depth (mbgl)	Blows (per 100mm)	Average Penetration per Blow (m)	Unit Point Resistance (MPa)	Dynamic Point Resistance (MPa)
5.10	5	0.02	9.43	5.53
5.20	5	0.02	9.43	5.49
5.30	4	0.03	7.54	4.35
5.40	5	0.02	9.43	5.40
5.50	5	0.02	9.43	5.36
5.60	4	0.03	7.54	4.25
5.70	6	0.02	11.32	6.33
5.80	5	0.02	9.43	5.23
5.90	5	0.02	9.43	5.19
6.00	5	0.02	9.43	5.15
6.10				
6.20				
6.30				
6.40				
6.50				
6.60				
6.70				
6.80				
6.90				
7.00				
7.10				
7.20				
7.30				
7.40				
7.50				
7.60				
7.70				
7.80				
7.90				
8.00				
8.10				
8.20				
8.30				
8.40				
8.50				
8.60				
8.70				
8.80				
8.90				
9.00				
9.10				
9.20				
9.30				
9.40				
9.50				
9.60				
9.70				
9.80				
9.90				
10.00				



Notes:

Hammer Mass	63.5 kg
Fall Height	0.76 m
Cone Area	0.0019 m ²
E _{theor}	473 J
Energy Ratio	0.757
Anvil Mass	0 kg
Rod Mass	8.79 kg/m

ASHDOWN SITE INVESTIGATION LTD


Dynamic Probe Record

SITE Emsworth Primary School, Victoria Road, Emsworth, Hampshire

Report Ref.

LW24121

Test Location Reference			WS2	
Depth (mblgl)	Blows (per 100mm)	Average Penetration per Blow (m)	Unit Point Resistance (MPa)	Dynamic Point Resistance (MPa)
0.10				
0.20	3	0.03	5.66	5.51
0.30	2	0.05	3.77	3.62
0.40	0.7	0.14	1.32	1.25
0.50	0.7	0.14	1.32	1.23
0.60	0.7	0.14	1.32	1.22
0.70	0.5	0.20	0.94	0.86
0.80	0.5	0.20	0.94	0.85
0.90	0.5	0.20	0.94	0.84
1.00	0.5	0.20	0.94	0.83
1.10	2	0.05	3.77	3.27
1.20	1	0.10	1.89	1.62
1.30	2	0.05	3.77	3.20
1.40	2	0.05	3.77	3.16
1.50	1	0.10	1.89	1.56
1.60	2	0.05	3.77	3.09
1.70	2	0.05	3.77	3.05
1.80	2	0.05	3.77	3.02
1.90	2	0.05	3.77	2.99
2.00	2	0.05	3.77	2.95
2.10	2	0.05	3.77	2.92
2.20	1	0.10	1.89	1.45
2.30	2	0.05	3.77	2.86
2.40	4	0.03	7.54	5.66
2.50	3	0.03	5.66	4.20
2.60	3	0.03	5.66	4.16
2.70	3	0.03	5.66	4.12
2.80	3	0.03	5.66	4.08
2.90	3	0.03	5.66	4.04
3.00	3	0.03	5.66	4.00
3.10	3	0.03	5.66	3.96
3.20	3	0.03	5.66	3.92
3.30	3	0.03	5.66	3.89
3.40	4	0.03	7.54	5.13
3.50	4	0.03	7.54	5.08
3.60	5	0.02	9.43	6.30
3.70	5	0.02	9.43	6.24
3.80	7	0.01	13.20	8.65
3.90	8	0.01	15.09	9.80
4.00	8	0.01	15.09	9.71
4.10	8	0.01	15.09	9.63
4.20	6	0.02	11.32	7.16
4.30	3	0.03	5.66	3.55
4.40	3	0.03	5.66	3.52
4.50	3	0.03	5.66	3.49
4.60	4	0.03	7.54	4.61
4.70	4	0.03	7.54	4.57
4.80	4	0.03	7.54	4.53
4.90	5	0.02	9.43	5.62
5.00	6	0.02	11.32	6.69



Notes:

Hammer Mass	63.5 kg
Fall Height	0.76 m
Cone Area	0.0019 m ²
E _{theor}	473 J
Energy Ratio	0.757
Anvil Mass	0 kg
Rod Mass	8.79 kg/m

ASHDOWN SITE INVESTIGATION LTD


Dynamic Probe Record

SITE Emsworth Primary School, Victoria Road, Emsworth, Hampshire

Report Ref.

LW24121

Test Location Reference			WS2	
Depth (mblgl)	Blows (per 100mm)	Average Penetration per Blow (m)	Unit Point Resistance (MPa)	Dynamic Point Resistance (MPa)
5.10	8	0.01	15.09	8.85
5.20	8	0.01	15.09	8.78
5.30	7	0.01	13.20	7.62
5.40	9	0.01	16.98	9.72
5.50	9	0.01	16.98	9.64
5.60	10	0.01	18.86	10.63
5.70	10	0.01	18.86	10.55
5.80	11	0.01	20.75	11.51
5.90	12	0.01	22.63	12.46
6.00	12	0.01	22.63	12.37
6.10				
6.20				
6.30				
6.40				
6.50				
6.60				
6.70				
6.80				
6.90				
7.00				
7.10				
7.20				
7.30				
7.40				
7.50				
7.60				
7.70				
7.80				
7.90				
8.00				
8.10				
8.20				
8.30				
8.40				
8.50				
8.60				
8.70				
8.80				
8.90				
9.00				
9.10				
9.20				
9.30				
9.40				
9.50				
9.60				
9.70				
9.80				
9.90				
10.00				



Notes:

Hammer Mass 63.5 kg
 Fall Height 0.76 m
 Cone Area 0.0019 m²
 E_{theor} 473 J
 Energy Ratio 0.757
 Anvil Mass 0 kg
 Rod Mass 8.79 kg/m

APPENDIX B

Geotechnical Laboratory Testing Notes

Laboratory Test Results

GEOTECHNICAL LABORATORY TESTING NOTES

1 Index Tests

Index (Atterberg Limit) tests are undertaken on samples of fine grained soils provide the primary information for the classification of fine grained soils.

Fine grained soil is tested to determine its liquid and plastic limits, which are moisture contents that define boundaries between material consistency states. These tests are used to evaluate indices used for soil identification and to help determine the shrinkage and swelling characteristics of the soil under conditions of changing moisture content. The tests are carried out in accordance with BS1377: Part 2: 1990 + A1:1996 Classification tests.

The consistency index is derived from the Index Tests and is summarized in the following table. These divisions may be approximate, particularly for low plasticity soils.

Consistency	Consistency Index
Very Soft	<0.25
Soft	0.25 to 0.50
Firm	0.50 to 0.75
Stiff	0.75 to 1.00
Very Stiff	>1.00

Based on BN EN ISO 14688-2:2004

2 Particle Size Distribution Tests

Sieve analyses are carried out soil samples to establish their particle size distribution that can assist in the assessment of the permeability and classification of granular soils.

The tests are carried out in accordance with BS1377: Part 2: 1990 + A1:1996 Classification tests.

3 Natural Moisture/ Saturated Moisture Content Determination of Chalk

The results of natural moisture or saturated moisture content tests of disturbed samples of chalk are used to assist in the classification of the chalk to determine key geotechnical parameters of strength, density and crushing properties.

The tests are carried out in accordance with BS1377: Part 2: 1990 + A1:1996 Classification tests.

4 Soil Suction Testing

Soil suction tests are undertaken for the determination of the state of desiccation in clay soils.

The testing is carried out in accordance with the Building Research Establishment Information Paper IP4/93, dated February 1993.

5 Triaxial Compression Tests

Undrained triaxial compression tests are carried out on undisturbed samples of cohesive soil in order to assist in the determination of the undrained shear strength of the soil. The results of moisture content and density determinations are also included.

The tests are carried out in accordance with BS1377: Part 7: 1990 + A1:1994 Shear strength tests (total stress).

6 Shear Vane and Hand Penetrometer Testing

Undisturbed samples are tested in the laboratory using a Geonor Hand Shear Vane for the determination of their undrained shear strength.

The vane tests are carried out in general accordance with BS1377: Part 7: 1990 + A1:1994 Shear strength tests (total stress).

7 One Dimensional Consolidation Tests

One-dimensional consolidation tests are performed on undisturbed soil samples to ascertain their settlement characteristics.

The tests are carried out in accordance with BS1377: Part 5: 1990 + A1:1994 Compressibility, Permeability and Durability tests.

8 Dry Density / Moisture Content Relationship (Compaction) Testing

Compaction testing for the determination of the dry density / moisture content relationship is carried out on using either a 2.5kg, 4.5kg hammer or a vibrating hammer.

The tests are carried out in accordance with the British Standard BS1377: Part 4: 1990 + A1 & A2:2002 Compaction-related tests.

9 California Bearing Ratio

The soil is usually compacted at the as dug "natural" moisture content and often at moisture contents around the natural moisture content.

The California bearing ratio is determined in accordance with the British Standard BS1377: Part 4: 1990 + A1 & A2:2002 Compaction related tests.

10 Chemical Testing

Soil samples are tested for their concentration of water soluble sulphate and pH for use in concrete mix design.

Water samples are tested for total sulphate concentration and pH value.

Where a water soluble sulphate content in soils or a total sulphate content in groundwater exceeds 3000mg/l SO_4 the magnesium sulphate content of the samples is required to be determined (BRE Special Digest 1:2005).

ASHDOWN SITE INVESTIGATION LTD


Site:	Emsworth Primary School, Victoria Road, Emsworth, Hampshire	Report No:	LW24121
		Sheet No:	1 of 1

SOIL CLASSIFICATION SUMMARY

Sample No.	Depth (m)	Nat. Moist. Cont. (w %)	Equiv. Moist. Cont. (w _s %)	Atterberg Limits			Class'n	Cons. Index (I _c)	% passing 425 µm sieve	Visual Description of Sample
				W _L %	W _p %	I _p %				
WS1	0.70	26	27	54	20	34	CH	0.59	98	Stiff brown and orange brown mottled black (iron-stained) slightly gravelly CLAY. Gravel is fine to medium flint
	5.00	20	23	58	18	40	CH	0.88	59	Stiff dark grey gravelly CLAY. Gravel is fine to medium flint and mudstone.
WS2	0.50	26	35	47	19	28	CI	0.44	75	Soft to firm brown sandy slightly gravelly CLAY. Gravel is fine to coarse flint.
	4.80	23	23	64	23	41	CH	1.00	100	Stiff grey highly calcareous CLAY.
TP1	0.90	32	32	49	20	29	CI	0.57	98	Soft brown slightly gravelly silty CLAY. Gravel is fine to medium flint.
TP2	0.60	22	27	36	18	18	CI	0.50	80	Firm dark brown and orange brown slightly sandy slightly gravelly CLAY. Gravel is fine to medium flint and ironstone.


Remarks:

Particle Size Distribution by Wet Sieve; BS1377: Part 2 1990



Job Name	Emsworth Primary School, Victoria Road, Emsworth, Hampshire.		BH/ TP No.	WS1	Sample Description
Job No.	LW24121		Sample Depth (m)	2.00	Very clayey SAND.


Particle Size Distribution by Wet Sieve; BS1377: Part 2 1990



Job Name	Emsworth Primary School, Victoria Road, Emsworth, Hampshire.		BH/ TP No.	WS1
Job No.	LW24121		Sample Depth (m)	4.00


Sample Description	Gravelly very clayey SAND.
-----------------------	----------------------------

Particle Size Distribution by Wet Sieve; BS1377: Part 2 1990



Job Name	Emsworth Primary School, Victoria Road, Emsworth, Hampshire.		BH/ TP No.	WS2	Sample Description
Job No.	LW24121		Sample Depth (m)	1.50	Very clayey SAND.

Particle Size Distribution by Wet Sieve; BS1377: Part 2 1990



Job Name	Emsworth Primary School, Victoria Road, Emsworth, Hampshire.		BH/ TP No.	WS2	Sample Description	Sandy CLAY.
Job No.	LW24121		Sample Depth (m)	3.50		



2683



2683

Unit A2
Windmill Road
Ponswood Industrial Estate
St Leonards on Sea
East Sussex
TN38 9BY
Telephone (01424) 718618
Facsimile (01424) 729911

THE ENVIRONMENTAL LABORATORY LTD

F.A.O. David Harris
Ashdown Site Investigation Limited
The Old Dairy, Swanborough Farm
Swanborough, Lewes,
East Sussex, BN7 9PF

Reporting Date: 19 June 2013

ANALYTICAL REPORT No. AR44939

Samples Received By: Laboratory Courier

Sample Receipt Date: 12/06/13

Your Job No: LW24121

Your Order No: 130337

Site Location: Emsworth Primary School, Victoria Road, Emsworth, Hampshire

No Samples Received: 4

Date of Sampling: 12/06/13

This report was written by: N. Williams

Authorised By;



Steve Knight
Reporting Manager

Any comments, opinions or interpretations expressed herein are outside the scope of UKAS accreditation (Accreditation Number 2683)



F.A.O. David Harris
Ashdown Site Investigation Limited
The Old Dairy, Swanborough Farm
Swanborough, Lewes,
East Sussex, BN7 9PF

THE ENVIRONMENTAL LABORATORY LTD

Unit A2, Windmill Road, Poveywood Industrial Estate, St Leonards-on Sea, East Sussex, TN38 9BY

Tel: 01424 718613 Fax: 01424 729911

ANALYTICAL REPORT No. AR44939

Location: Emsworth Primary School, Victoria Road, Emsworth, Hampshire



Your Job No: LW24121
Your Order No: 130337
Reporting Date: 19/06/13

Soils

Characteristic	Loamy sand	Sand	Sand	Loamy sand
Date Sampled	12/06/13	12/06/13	12/06/13	12/06/13
TP/BH	WS1	WS1	WS1	WS2
Depth (m)	1.20	3.00	4.00	2.50
Our ref	73686	73687	73688	73689
Stone Content (%)	<1	<1	<1	<1
pH Value** (Units)	8.0	8.5	8.6	8.5
Total Sulphate (% as SO ₄)	<0.05	0.06	0.07	0.06
Total Sulphur (% as S)	<0.05	<0.05	<0.05	<0.05
Water Soluble Sulphate (mg/l as SO ₄)	<20	<20	<20	<20
Water Soluble Chloride (mg/l)	<20	<20	<20	<20
Water Soluble Nitrate (mg/l)	<20	<20	<20	<20
Water Soluble Sulphate** (mg/kg SO ₄)	<40	<40	<40	<40
Water Soluble Chloride** (mg/kg)	<40	<40	<40	<40
Water Soluble Nitrate** (mg/kg)	<40	<40	<40	<40
Water Soluble Magnesium (mg/l)	0.3	0.3	0.2	0.2
Ammonium (mg/l)	<0.1	<0.1	<0.1	<0.1

All results expressed on dry weight basis

** - MCERTS accredited test

* = UKAS accredited test

N. Williams

THE ENVIRONMENTAL LABORATORY LTD

SAMPLE RECEIPT AND TEST DATES

Our Analytical Report Number AR44939
Your Job No: LW24121
Sample Receipt Date: 12/06/13
Reporting Date: 19/06/13

Registered: 12/06/13
Prepared: 13/06/13
Analysis complete: 19/06/13

TEST METHOD SUMMARY

PARAMETER	Analysis Undertaken on	Date Tested	Method Number	Technique
pH Value**	Air dried sample	17/08/13	113	BRE SD1
Total Sulphate	Air dried sample	14/08/13	115	BRE SD1
Total Sulphur	Air dried sample	14/08/13	216	BRE SD1
Water Soluble Sulphate	Air dried sample	17/08/13	172	BRE SD1
Water Soluble Nitrate	Air dried sample	17/08/13	172	BRE SD1
Water Soluble Chloride	Air dried sample	17/08/13	172	RRF SD1
Water Soluble Magnesium	Air dried sample	17/08/13	101	BRE SD1
Ammonium	As submitted sample	14/08/13	151	BRE SD1

* = UKAS Accredited test

** - MCERTS Accredited test

Determinands not marked with * or ** are non accredited

MCERTS accreditation covers samples which are predominantly sand, clay, loam or combinations of these three soil types

Any comments, opinions, or interpretations expressed herein are outside the scope of UKAS accreditation (Accreditation Number 2683)

APPENDIX C

Hampshire County Council Geotechnical Work
Package Information:

1:2,500 Site Plan

1:500 Site Plan

Aerial Photograph

Superficial Geology

Bedrock Geology

Epoch 1 (1843 -1893)

Epoch 2 (1891 - 1912)

Epoch 3 (1904 - 1939)

Epoch 4 (1919 - 1943)

Survey with Service Information

Proposed Site Plans

0 25 50 100 Meters

1:2,500



Emsworth Primary School

Hampshire
County Council

0 25 50 100 Meters

1:2,500



Emsworth Primary School

Hampshire
County Council

0 5 10 20 Meters 1:500

MP 36

Emsworth
Primary School

© Crown Copyright 2005 HCC 100019180
Reproduced from the Ordnance Survey
map with the permission of the controller
of Her Majesty's Stationery Office

Legend

Emsworth Primary School



Hampshire
County Council

0 10 20 40 Meters

1:1,000



© Crown Copyright 2005 HCC 100019180
Reproduced from the Ordnance Survey
map with the permission of the controller
of Her Majesty's Stationery Office

Legend

Emsworth Primary School




Hampshire
County Council

0250100150 Meters

1:10,000

HEAD (UNDIFFERENTIATED)

HEAD (UNDIFFERENTIATED)



HEAD (UNDIFFERENTIATED)

RIVER TERRACE DEPOSITS (UNDIFFERENTIATED)

ALLUVIUM

HEAD (UNDIFFERENTIATED)

HEAD (UNDIFFERENTIATED)

RAISED MARINE DEPOSITS (UNDIFFERENTIATED)

HEAD (UNDIFFERENTIATED)

BEACH AND TIDAL FLAT DEPOSITS (UNDIFFERENTIATED)


© Crown Copyright 2005 HCC 100019180
 Reproduced from the Ordnance Survey
 map with the permission of the controller
 of Her Majesty's Stationery Office

474000

475000

0250100150 Meters

1:10,000



Emsworth Primary School
Bedrock Geology




Hampshire
County Council

474000 000000

0 50 100 200 Meters

1:5,000




Emsworth Primary School
Epoch 1 1843-1893



Hampshire
County Council

0 50 100 200 Meters

1:5,000



Emsworth Primary School
Epoch 2 1891-1912




Hampshire
County Council

474000 000000

0 50 100 200 Meters

1:5,000



Emsworth Primary School
Epoch 3 1904-1939




Hampshire
 County Council

0 50 100 200 Meters

1:5,000

L I N G T O N U D.

B L I N G T O N





EMSWORTH PRIMARY SCHOOL

Final

EMSWORTH PRIMARY SCHOOL
Countryside
Final

Project: Emsworth Primary School
Client: Emsworth Primary School
Date: 01.01.2024
Scale: 1:500
Sheet: 001 of 001

Drawn by: [Name]
Checked by: [Name]
Approved by: [Name]

Project Manager: [Name]
Project Engineer: [Name]
Project Designer: [Name]

Project Location: [Address]
Project Reference: [Reference]

EMSWORTH PRIMARY SCHOOL
Countryside
Final

Project: Emsworth Primary School
Client: Emsworth Primary School
Date: 01.01.2024
Scale: 1:500
Sheet: 001 of 001

Drawn by: [Name]
Checked by: [Name]
Approved by: [Name]

Project Manager: [Name]
Project Engineer: [Name]
Project Designer: [Name]

Project Location: [Address]
Project Reference: [Reference]



Emsworth Primary School

School Expansion to 1.5 F.E.

Location Plan



PLANNING



HCC Property Services,
Three Minster's House,
78 High Street, Winchester SO23 8UL.
Tel: (01562) 847801

Notes	
1	This drawing is © copyright Hampshire County Council 2012. No unauthorised reproduction is permitted. All rights reserved.
2	No derivations are to be scaled from this drawing.
3	This map is reproduced from Ordnance Survey material with the permission of Ordnance Survey on behalf of the controller of Her Majesty's Stationery Office & Crown Copyright. Unauthorised reproduction infringes Crown Copyright and may lead to prosecution or civil proceedings. (100019100), (2012)

rev	description	date	by

PROJECT		SHEET CONTENTS	
Emsworth Primary School Two Classroom Extension		Location Plan	
SCALE	1:1000 @ A1 1:2000 @ A3	DATE	03/08/12
DRAWN	arons	CHECKED	—
DRAWING NO	P09163 A 001	PROPERTY SERVICES	RELATION
FILE REF.	P09163 A 001		



Emsworth Primary School

School Expansion to 1.5 F.E.

Proposed Site Plan

- Key
- Site Boundary 2.12 ha
 - Work Boundary and contractors compound 1804 m²
 - New build
 - Alterations to existing buildings
 - Demolition
 - No work to existing buildings
 - Existing Pedestrian Access
 - Existing Vehicular Access



PLANNING



PROJECT	Emsworth Primary School Two Classroom Extension				SHEET CONTENTS	
	Proposed Site Plan				Property Services	
SCALE	1:500 @ A1	DATE	20/08/12	DRAWN	CH-ED	DRAWING NO
	1:1000 @ A3			arons	—	P09163 A 003
					FILE REF.	PO9163 A 001

REV	DESCRIPTION	DATE	BY

Notes	
1. This drawing is the copyright of Hampshire County Council 2012. No unauthorised reproduction is permitted. All rights reserved.	2. This map is reproduced from Ordnance Survey material with the permission of Ordnance Survey on behalf of the Controller of Her Majesty's Stationery Office. Crown Copyright. Unauthorised reproduction infringes Crown Copyright and may lead to prosecution or civil proceedings. (100019 000), (2012)



Property Services

Emsworth Primary School

School Expansion to 1.5 F.E.

Proposed Site Plan

Key

Site Boundary 2.12 ha

Work Boundary and contractors compound 1804 m²

New build

Alterations to existing buildings

Demolition

No work to existing buildings

Existing Pedestrian Access

Existing Vehicular Access

North



0m 25m 50m

PLANNING

PROJECT: Emsworth Primary School Two Classroom Extension		SHEET CONTENTS: Proposed Site Plan	
SCALE 1:500 @ A1 1:1000 @ A3	DATE 20/09/12	DRAWN BY/PCS	CHECKED —
DRAWING No P09163 A 003		PROPERTY SERVICES HEADER	
FILE REF. P09163 A 003			

Item	Description	Date	By

NOTES	
1	This map is reproduced from Ordnance Survey material with the permission of Ordnance Survey on behalf of the Controller of Her Majesty's Stationery Office. Crown Copyright. Unauthorised reproduction infringes Crown Copyright and may lead to prosecution or civil proceedings. (1000191000, 12/02)
2	No dimensions are to be scaled from this drawing

**Hampshire County Council**

HCC Property Services
The Hub, 76 High Street, Winchester SO23 9LA
tel: 01902 947601

SINGLE STORY

BUILDING EXPECTED

FOUNDATION LANDING 40KN/101

FOUNDING STRATA

NO REQUIRED FOR NEW

BUILD

Emsworth Primary School

