



SUSTAINABILITY & ENERGY STATEMENT

Proposed Conversion and Part New Build Development

270 London Road

1. Existing Building Performance

- a. The existing building has an Energy Performance Certificate (EPC) rating of D, indicating moderate energy efficiency with clear opportunity for improvement.
- b. The proposed development comprises:
- c. Conversion of the Front Block to form 4 studio flats and a ground floor gym.
- d. Part new build and conversion of the Rear Block to form 10 co-living studio bedrooms with gym training space.
- e. The scheme adopts a fabric-first approach, combined with low-carbon heating systems and renewable energy generation, to significantly enhance thermal and acoustic performance while reducing operational carbon emissions.

2. Energy & Sustainability Strategy

- a. The strategy prioritises:
- b. Reduction in energy demand through enhanced insulation and airtightness.
- c. Upgrading the thermal envelope beyond existing standards.
- d. Use of efficient electric Infrared heating systems.
- e. On-site renewable energy generation.
- f. Integrated energy storage solutions.

3. FRONT BLOCK – Conversion to 4 Studio Flats & Gym

- a. Fabric Improvements
- b. Internally to external Walls & Windows
- c. New insulated cavity wall construction to the gym frontage.
- d. New double-glazed gym frontage windows.
- e. Secure by Design entrance door.

- f. 1st floor front-facing glazing to be checked and upgraded where required to 4-20-6 acoustic glazing units.
- g. 2nd floor front-facing and rear-facing existing windows to be replaced with new 4-20-6 acoustic glazing units.
- h. All upgraded glazing improves both thermal efficiency and acoustic attenuation given the London Road location.

4. Internal Insulation & Finishes

- a. All internal cavity walls to 1st and 2nd floors to be internally clad with additional insulation to reduce heat loss and improve airtightness.
- b. Finished with acoustic plasterboard, tape and jointed, improving both thermal retention and sound separation.
- c. Ceilings beneath 1st and 2nd floors upgraded in accordance with the submitted Acoustic Specification and finished with acoustic plasterboard.
- d. Loft above 2nd floor to receive 2 x 200mm insulation quilt (400mm total) to significantly reduce heat loss through the roof.
- e. These measures will substantially improve U-values compared to the existing EPC D baseline.

5. Heating & Hot Water

- a. Heating via high-efficiency ceiling-mounted infrared heating panels, providing radiant heat rather than convected heat.
- b. Zoned temperature controls to prevent excessive sustained heating.
- c. Each studio to be provided with an efficient Air Source Hot Water Cylinder, significantly reducing carbon emissions compared to conventional direct electric systems.

6. Renewable Energy

- a. Subject to SAP calculations, PV panels will be installed to the rear pitched roof to offset electrical demand.

7. REAR BLOCK – Part New Build & Conversion (10 Co-Living Studios)

- a. Fabric-First Construction
 - i. Ground Floor
 - ii. New concrete floors overlaid with 100mm insulation and 75mm screed.
 - iii. Existing ground floor walls internally insulated and finished with acoustic plasterboard, tape and jointed to improve thermal and acoustic performance.
 - iv. Upper Floors (Timber Frame)

- v. 140mm timber studs with 120mm PIR insulation installed between studs.
 - vi. Overlaid with additional 25mm PIR insulation.
- b. Finished internally with acoustic plasterboard, tape and jointed, enhancing sound separation between units.
- c. Roof Construction
 - i. Warm roof comprising:
 - ii. 150mm PIR insulation
 - iii. 100mm vertical perimeter PIR insulation to minimise thermal bridging
 - iv. 60-minute fire-resistant single-ply roof covering

8. Renewable Energy & Storage

- a. Approximately 10–11 kW Solar PV array to flat roof.
- b. Correctly sized inverters.
- c. Battery storage sized to:
 - i. Store excess PV generation.
 - ii. Supply evening demand.
 - iii. Enable off-peak tariff charging.
- d. 4 x 250 litre Air Source Hot Water Cylinders (2 per upper floor service cupboard).
- e. Cylinders act as thermal storage where PV output exceeds battery capacity.
- f. This integrated system maximises on-site renewable energy use and reduces grid demand.

9. Heating & Ventilation

- a. Heating via ceiling-mounted high-efficiency infrared heating panels throughout bedrooms and communal areas.
- b. Intelligent controls limiting extended high temperature operation.
- c. All bedrooms provided with single-room MVHR units, reducing ventilation heat loss while maintaining indoor air quality.
- d. Carbon Reduction & EPC Improvement
- e. The scheme transforms an existing EPC D rated building through:
 - i. Significant insulation upgrades.
 - ii. Improved airtightness.
 - iii. Acoustic and thermal glazing upgrades.
 - iv. Electrification of heating and hot water.
 - v. On-site renewable energy generation.
 - vi. Battery and thermal storage integration.
 - vii. MVHR heat recovery systems.
- f. A substantially improved EPC rating is anticipated (subject to SAP confirmation).

10. Ecology Enhancements

- a. Integrated swift boxes will be installed
- b. Integrated bat boxes will be installed
- c. Rear courtyard to be redeveloped incorporating
 - i. Installation of planters with pollinator friendly species
 - ii. Climbing planters to improve vertical habitat
 - iii. Use of permeable finishes where appropriate to support sustainable drainage
 - iv. Water butt for rainwater harvest and to support ease of watering planters for tenants.

11. Conclusion

- a. The proposed development delivers a comprehensive sustainability-led retrofit and new-build approach. The combination of enhanced thermal envelope performance, acoustic plasterboard finishes, renewable energy generation, battery storage, and low-carbon heating systems ensures:
 - i. Reduced operational carbon emissions
 - ii. Improved thermal and acoustic comfort
 - iii. Lower long-term energy costs
 - iv. Future-proofed low-carbon infrastructure
- b. The development accords with national and local planning policies promoting sustainable construction and energy efficiency.