People and Organisation

Best Start in Life Family Hubs

signage proposals

February 2026

Hampshire County Council

Interior Design, Property Services

BSiL Family Hubs – guidance, templates & specifications

External signage:

Typically:

- Dibond material, with anti-graffiti laminate, radius cornered
- Mechanical fixings into brick (4 or 6 screws and white caps), site specific
- Vinyl graphics to glazing or surfaces where a fixed sign is not suitable
- Matched height of existing building signage where appropriate, so as not to overwhelm building main usage.

BSiL Family Hubs - branding

Example sign, internal and external use. Directional arrows to be added as necessary

Example internal sign (1no. must have Govt logo and ‘Funded by UK Government’ text included)

Branding for internal pull-up banners, leaflets, posters, etc..

Leigh Park Library – proposed external signs

1x Dibond sign, anti-graffiti laminate, radius cornered, mechanical fixings into brick (4 or 6 screws and white caps), to left hand side of existing library sign, matched height (400H x 745W)

Main Entrance, Park Parade

Leigh Park Library – proposed external signs

amended size and location of the sign adjacent to the main entrance

Fixed sign to right hand side of existing library sign, matched height (400H x 300W)

Detail: Fixed sign to right hand side of existing library sign, matched height (400H x 300W)

Main Entrance, Park Parade

Leigh Park Library – proposed external signs

2x Dibond signs, anti-graffiti laminate, radius cornered, mechanical fixings into brick (4 or 6 screws and white caps), to left hand sides of existing library signs, matched heights (580H x 1080W, 400H x 745W)

Park Parade

Leigh Park Library – proposed external signs

2x Dibond signs, anti-graffiti laminate, radius cornered, mechanical fixings into brick (4 or 6 screws and white caps), to left and right hand sides of existing library signs, matched heights (580H x 1080W)

Dunsbury Way

Leigh Park Library – proposed external signs

Detail: 2x Dibond signs, anti-graffiti laminate, radius cornered, mechanical fixings into brick (4 or 6 screws and white caps), to left and right hand sides of existing library signs, matched heights (580H x 1080W)

Dunsbury Way

Leigh Park Library – proposed external signs

1x Dibond sign, anti-graffiti laminate, radius cornered, mechanical fixings into brick (4 or 6 screws and white caps), to left hand side of existing 'Community Suite' sign, matched height (450H x 835W)

Rear Out of Hours Entrance

Leigh Park Library

Basing Road (no works)