




HR3500 HEAT RECOVERY UNIT

INSTALLATION, OPERATION & MAINTENANCE INSTRUCTIONS



PLEASE READ THESE INSTRUCTIONS CAREFULLY BEFORE ATTEMPTING INSTALLATION

Biddle GmbH
Emil – Hoffmann – Straße 55-59
50996 Köln
Deutschland

Email: info@biddle.de
T: +49 (0)2236 9690-0
F: +49 (0)2236 9690-10
<http://www.biddle.de>

English

Biddle HR3500 Heat Recovery Unit

CONTENTS

	Page
DESIGN	
Heat Recovery Unit System Schematics	3
Figure 1 - System 1 with NOZ25 Unit Heaters	3
Figure 2 - System 2 with CC90 Cassette Heaters	4
Design Information	5
Operating Mode 1 to 4 - explanation	5
Figure 3 – Dimensions of HR3500 Heat Recovery Unit	6
Fan speed voltage and airflow performance data	7
Electrical supply and electrical data	8
Heat recovery data	9
Noise level data and ErP product information	10
Condensate Drainage	11
Dirty filter indication system	12
INSTALLATION	
Unpacking the Heat Recovery Unit	13
Installation of the Heat Recovery Unit	15
Condensate Disposal System	17
Electrical supply and control wiring	18
Wiring Diagram 1 – Site Wiring	20
COMMISSIONING	
Inspect the outside of the Heat Recovery Unit	21
Check the inside of the Heat Recovery Unit	21
Setting fan speeds	23
Site BMS and hand-over to End-User	25
SERVICING	26
FAULT FINDING	29
WARRANTY	30
EC DECLARATION OF CONFORMITY	31

Heat Recovery Unit System Schematics

The HR3500 Heat Recovery Unit can be used in one of the following two systems to provide a fresh air system with heat recovery and heating of the supermarket:

System 1. with Biddle NOZ25V-W6-E-D0-HR Unit Heaters

System 2. with Biddle CC90V-H3-D0-HR Cassette Heaters

System 1. HR3500 - NOZ25 Heat Recovery System

Ductwork and Controls Schematic:-




Figure 1

System 2. HR3500 - CC90 Heat Recovery System

Ductwork and Controls Schematic :-




Figure 2

DESIGN INFORMATION

The HR3500 Heat Recovery Unit is an air handling unit containing fans, filters, air-to-air plate heat exchanger, dampers, controls and ductwork connections. It is designed to integrate into the fresh air and extract air systems that serve a supermarket and recover waste heat from the extract air coming from the supermarket that would otherwise have been lost to outdoors.

The HR3500 Heat Recovery Unit can be used with:

1. Biddle NOZ25V-W6-E-D0-HR Unit Heaters in stores where Biddle NOZ unit heaters are used for heating the store. See Figure 1.
2. Biddle CC90V-H3-D0-HR Cassette Heaters in stores where Biddle CC unit heaters are used for heating the store. See Figure 2.

The control strategy and fan speed selection of the Heat Recovery Unit is carried out automatically by the site BMS controller which is located in the offices of the store. 24V AC control signals are sent via hard-wired cables from the site BMS to the electric control box on the Heat Recovery Unit to provide the following modes of operation with fan speed selection:

Mode 1 – Full Heat Recovery with fresh air and room extract air passing through the heat exchanger

Supply Fan	Extract Fan	Fresh Air Damper	Exhaust Damper	Recirculation Damper	Summer By-Pass Damper
ON High, Medium or Low fan speed	ON High or Low fan speed	OPEN	OPEN	CLOSED	CLOSED to By-Pass

Mode 2 – Full Recirculation, no fresh air or exhaust air to outside

Supply Fan	Extract Fan	Fresh Air Damper	Exhaust Damper	Recirculation Damper	Summer By-Pass Damper
ON High, Medium or Low fan speed	OFF	CLOSED	CLOSED	OPEN	CLOSED to By-Pass

Mode 3 – Night Cooling in warm weather periods to reduce air temperatures in the supermarket during the next day

Supply Fan	Extract Fan	Fresh Air Damper	Exhaust Damper	Recirculation Damper	Summer By-Pass Damper
ON Medium fan speed only	ON Medium fan speed only	OPEN	OPEN	CLOSED	OPEN to By-Pass

Mode 4 – Smoke Extract (not always programmed in the site BMS)

Supply Fan	Extract Fan	Fresh Air Damper	Exhaust Damper	Recirculation Damper	Summer By-Pass Damper
OFF	ON High fan speed only	CLOSED	OPEN	CLOSED	CLOSED to By-Pass

Please Note. The unit and its components are not temperature rated for smoke extract so will only provide a limited period of operation under smoke conditions.




FIGURE 3 – DIMENSIONS OF HR3500 HEAT RECOVERY UNIT

Fan Speed Voltage and Airflow Performance Data

There are two EC fans in the HR3500 Heat Recovery Unit, a Supply Fan and an Extract Fan. Figures 4 and 5 show the airflow performance of these two fans at different DC control voltages. The design system curve for 3500m³/h is also shown for each fan.

Figure 4





Figure 5



Electrical Supply and electrical data

The HR3500 Heat Recovery Unit operates on a 1 phase electrical supply (1L+N+E) from a local switched spur which provides electrical power for fans and control equipment in the unit. The electrical installation should be sized in accordance with the following:

Electrical Supply = 230v / 1ph / 50Hz

Rated Electrical Power Input = 2760 W (with both fans on maximum speed - 10V DC)

Rated Current = 12.0 A (with both fans on maximum speed - 10V DC)

There are two fans in the unit, a Supply Fan and an Extract Fan, and during commissioning the High, Medium and Low speed settings for each fan is set by the commissioning Engineer. Figure 4 and Figure 5 show the air volume flow rate against the external static pressure for both fans for a range of DC control voltages from 5v to 10v. The commissioning engineer will set the control voltage on site to achieve the air volume flow rate they require from each fan. It is preferable to aim for the same airflow from each fan as this then gives the highest heat exchange efficiency.

As an indication, Tables 1 and 2 give electrical data for each fan operating along its design system curve, see also Figures 4 and 5.

Table 1 - Supply Fan on the 3500m³/h - 300Pa system curve (see Figure 4)

Control Voltage (DC Volts)	Air Volume Flow Rate (m ³ /h)	Power Input (W)	Current (A)	SFP (W/m ³ /s)
10.0 high	3500 (at 300Pa)	1350	5.56	1370
9.5	3430	1245	5.20	1300
9.0	3335	1155	4.92	1250
8.5	3185	1005	4.24	1140
8.0 medium	3025	875	3.68	1040
7.5	2830	740	3.10	930
7.0	2595	605	2.58	840
6.5	2380	495	2.12	760
6.0 low	2110	360	1.56	610
5.5	1870	285	1.28	570
5.0	1710	245	1.13	510

Table 2 - Extract Fan on the 3500m³/h - 150Pa system curve (see Figure 5)

Control Voltage (DC Volts)	Air Volume Flow Rate (m ³ /h)	Power Input (W)	Current (A)	SFP (W/m ³ /s)
10.0 high	3500 (at 150Pa)	1290	5.14	1320
9.5	3390	1200	4.98	1270
9.0	3295	1090	4.50	1190
8.5	3095	955	3.97	1110
8.0 medium	2920	815	3.38	1010
7.5	2720	705	2.96	930
7.0	2530	590	2.52	840
6.5	2325	475	2.00	740
6.0 low	2110	370	1.62	630
5.5	1920	295	1.34	560
5.0	1720	230	1.07	480

high/medium/low as set in software, can be changed during commissioning.

Heat Recovery

The unit operates in heat recovery when it is in Mode 1 to recover the waste heat energy in the extract air path. Figure 6 shows how much heat energy is recovered for different air volume flow rates and Figure 7 shows the efficiency of the heat exchanger. Both the supply fan and extract fan have the same air volume flow rates in Figure 6 and 7 as this gives the maximum heat recovery and efficiency for each volume flow rate.

Figure 6





Figure 7



Noise Level Data

Table 3 gives the maximum In-Duct Sound Power Levels (L_W) for when the Supply Fan is operating at 3500m³/h at 300Pa external static pressure and when the Extract Fan is operating at 3500m³/h at 150Pa external static pressure.

Table 3 – Maximum In-Duct Sound Power levels, Mode 1

Sound Power Level (L_W re. 10^{-12} W)	Octave Band Centre Frequency (Hz)								L_{WA} dB(A)
	63	125	250	500	1000	2000	4000	8000	
Supply Air to Store	75.8	70.7	78.6	78.4	81.3	81.2	78.3	75.4	86.6
Extract Air from Store	68.6	65.8	75.5	72.3	69.2	70.2	68.2	67.2	76.7
Exhaust Air to Outside	75.8	70.7	78.6	78.4	81.3	81.2	78.3	75.4	86.6
Fresh Air from Outside	68.6	65.8	75.5	72.3	69.2	70.2	68.2	67.2	76.7

Casing Sound Power Level, dB(A) (L_{WA} re. 10^{-12} W):

10V DC (High Speed) = 74 dB(A)

8V DC = 69 dB(A)

6V DC = 64 dB(A)

5V DC = 60 dB(A)

For a typical Store:

Sound Pressure Level, dB(A) (L_{PA} re. 2×10^{-5} N/m²) measured at 1m from underside of unit:

10V DC (High Speed) = 66 dB(A)

8V DC = 61 dB(A)

6V DC = 56 dB(A)

5V DC = 52 dB(A)

Ecodesign (ErP) Ventilation Units – product information

Manufacturer: Biddle Air Systems Ltd.

Model: HR3500

Type: Non Residential Ventilation Unit – Bidirectional Ventilation Unit (NRVU-BVU)

Drive: Variable Speed Drive (VSD)

Heat Recovery System: Regenerative Plate Heat Exchanger

Thermal Efficiency of Heat Recovery (η_{t_nrvu}): 89.3%

Nominal Flow Rate (q_{nom}): 0.97m³/s Maximum

Effective Electric Power Input: 1.35 kW Maximum

Specific Fan Power (SFP_{int}): 1370 W/m³/s Maximum

Filter Face Velocity: 2.1m/s Typical; 2.4m/s Maximum

Nominal External Pressure ($\Delta p_{s, ext}$): 300Pa Maximum

Internal Pressure Drop ($\Delta p_{s, int}$): 440Pa Maximum

Static Fan Efficiency (η_{es}): 59.4%

Maximum External Leakage Rate: 3.3 l/s

Maximum Internal Leakage Rate: 0.92 l/s

Filter Energy Performance: 779kWh/year Typical; 1906kWh/year Maximum

Visual Filter Warning: Indicator light on unit + BACnet Comms alarm

IMPORTANT: Regularly change filters for performance and energy efficiency of unit

Casing Sound Power Level (L_{WA}): 64dB(A) Typical; 74dB(A) Maximum

Internet Address for disassembly instructions: <http://www.biddle-air.co.uk>

Condensate Drainage

The Heat Recovery Unit is supplied with an integral condensate drain tray fitted inside the unit to catch condensate that will form within the heat exchanger during operation in cold weather. The drain tray feeds into a 15mm condensate drain pipe that projects from one side of the unit (see Figure 3). The Installer should fit a condensate drain trap and condensate pipework to the 15mm drain pipe and extend it to a suitable drain, see pictures on Page 17. The condensate drain trap and pipework are the responsibility of the installer and the trap must be designed as shown in Figure 8.




Figure 8

It is normal to drain the condensate by gravity and the condensate disposal system should be extended at a suitable gradient (1 in 50) to a convenient drain in the store room, normally adjacent to the condensing boiler.

Warning: The condensate collection system is designed to remove condensate with the Heat Recovery Unit operating during normal winter weather conditions in countries with a temperate climate. In case of extreme weather conditions, blockage of the drain tray or condensate trap, which are conditions that can occur, it is vital that the design of the floor beneath the Heat Recovery Unit and its surface is such that it will not become slippery or damaged if it became wet. Do not store items under the unit that could be damaged by condensate water if this were to occur. Ceiling tiles could also be damaged by condensate water if this were to occur.

Dirty Filter Indication System

A dirty filter indication system is incorporated into the Heat Recovery Unit to show when the air filters need cleaning or replacing. The dirty filter indicator light is fitted near the hinged door on the edge of the supply fan section, see Figure 9.



Figure 9

If used, the BACnet comms. will also indicate an alarm when the dirty filter indication system triggers.

Once the dirty filter indication system triggers to show dirty filters the indicator light will stay on until the filters are changed and the indication system is reset. Reset is done by switching electrical power to the unit Off and back On again.

IMPORTANT: Dirty air filters waste energy. Regular air filter changes are important for the correct performance and energy efficiency of the unit

If the Heat Recovery Unit operates during cold weather in Mode 1 (Heat Recovery) cold fresh air will enter the fresh air intake and ice could form in some sections of the unit particularly the plate heat exchanger. There is a differential pressure switch that detects the air pressure across the heat exchanger, if it gets too high because of ice blocking the airways the controller in the unit will go into defrost mode for approximately 10 minutes so that warm air from the building can defrost the sections of the unit where ice may be building up.

Any frost protection strategy to protect the water heating coil in the Biddle NOZ25 or CC90V Heater must be done by the Site BMS. The Heat Recovery Unit is unable to frost protect the heating coil in the NOZ25 or the CC90V Heater.

The Heat Recovery Unit is designed only for use in Stores as designated for a Biddle heat recovery system. The complete Biddle heat recovery system, including ductwork, condensate drain system, water pipework, wiring, controls, etc. must be installed only by an approved contractor.

Persons using the Heat Recovery Unit must be given adequate instruction and supervision concerning the use of the appliance by a person responsible for their safety. The Heat Recovery Unit is not intended for use by persons (including children) with reduced physical, sensory or mental capabilities.

These instructions must be read in conjunction with the separate Biddle instructions that come with other components of the heat recovery/heating system, e.g. NOZ25 Unit Heater, CC90V Cassette Heater and other Biddle ancilliary equipment. All instructions should be kept by the building facilities manager for future reference.

UNPACKING THE HEAT RECOVERY UNIT

Unpack as shown:-

1



Extract Fan Section
120kg

Supply Fan Section
195kg

Heat Exchanger Section
275kg

The following items are supplied with the HR3500 Heat Recovery Unit:-

2



**M8 x 30mm Bolts, Washers
and Nuts**

3



Self-Adhesive Mini Trunking

If anything is missing or damaged please contact your place of purchase immediately.

The Installer will also need to supply and install the following:-

Condensate Drain System



Condensate Drain Trap

Must have drain trap here or somewhere in the condensate drain system



The complete Biddle heat recovery system, including ductwork, condensate drain system, water pipework, wiring, controls, etc. must be installed only by a competent contractor.

IMPORTANT

The heat recovery unit is intended only for use in stores as part of a Biddle heat recovery system.

These instructions must be read in conjunction with the separate Biddle instructions that come with other components of the heat recovery/heating system, e.g. NOZ25 Unit Heater, CC90V Cassette Heater and other Biddle ancilliary equipment.

All instructions should be kept by the building facilities manager for future reference.

For your records:

Date of Purchase.....

Place of Purchase.....

Serial Number.....


For warranty purposes proof of purchase is necessary so please keep a copy of your invoice.

INSTALLATION OF THE HEAT RECOVERY UNIT

The heat recovery unit is designed to be mounted inside the stock room of a retail store suspended from the ceiling on hanging rods. It must not be installed on the outside of the building or in any other location.


Determine the mounting position and location for the heat recovery unit.
See Figure 3 for dimensions of the unit.

Lift the Heat Exchanger Section (275kg*) into position, see picture




Attach the Heat Exchanger Section to the ceiling using 4 x M10 threaded hanging rods fixed to 4 x hanging brackets on the unit. Suitable ceiling fixings need to be used to fix the M10 threaded hanging rods, taking into account the type of fixing and the weight of the unit, see picture.

All 4 suspension points must be used.



Lift the Extract Fan Section (120kg*) into position adjacent to the Heat Exchanger Section as shown in the picture. Make sure there is rubber sealing strip fitted between each Section.

The Extract Section is attached to the ceiling with 2 x M10 threaded hanging rods and by bolting to the heat exchanger section. Both of



Bring the Extract Fan Section together towards the Heat Exchanger section, see picture.

Ensure the four alignment bolts, which are fitted along the bottom edge of the Heat Exchanger Section correctly line up with the corresponding holes on the bottom edge of the Extract Fan Section.



With the Heat Exchanger and Extract Fan Sections secure, lift and position the Supply fan Section (195kg*) into place, see picture. Make sure there is rubber sealing strip between each Section.

The Supply Fan Section is attached to the ceiling with 2 x M10 threaded hanging rods and by bolting to the Heat Exchanger Section. Both of the suspension points must be used.


Ensure the two bottom alignment bolts, which are fitted along the bottom edge of the Heat Exchanger Section, line up with the corresponding holes on the Supply Fan Section, see picture.

* It is the sole responsibility of the installer to ensure that the building fixing locations and suspension system used are suitable for the weight of the Heat Recovery Unit.

Using the brackets bolt all three sections together using the nuts and bolts supplied, see picture.

With all three sections of the HR3500 Heat Recovery Unit joined together and suspended from the ceiling, adjust the hanging rods so the bottom of the whole unit is level. The unit must be installed level or condensate may leak out during cold weather.

Picture shows the complete unit installed ready for connection of ductwork, electrical power and control wiring.



Condensate Disposal System

Condensate Drain System



Condensate Drain Trap

Must have drain trap here or somewhere in the condensate drain system



Install the condensate drain system from the 15mm condensate drain trap

It is normal to drain the condensate by gravity and the condensate disposal system should be extended at a suitable gradient (1 in 50) to a convenient drain in the store room, normally adjacent to the condensing boiler. It is important that the condensate trap is filled with water or condensate may not drain away and cause water damage inside the unit or leak out of the unit, see section Commissioning, Page 21.

The condensate drain trap and pipework are the responsibility of the installer and the trap must be designed as shown in Figure 10.




Figure 10

Electrical Supply and Control Wiring to the Heat Recovery Unit

All electrical wiring and connections MUST be carried out by a competent qualified electrician in accordance with the latest edition of wiring regulations and/or local statutory regulations. (see also Wiring Diagram 1 on Page 20)

A 230V, 15 Amp rated, 1 phase electrical supply (1L + N + E) must be connected to the input terminals of the local 2-pole isolator switch that is pre-fitted to the side of the heat recovery unit. The unit must have an Earth connection.



Remove the red handle, as shown in picture, then the yellow collar and then the white case from the electrical isolator switch.



Connect electrical supply:

Blue Neutral wire – Terminal 1

Brown Live wire – Terminal 3

Green/Yellow wire – Earth Terminal

Replace case, collar and handle of isolator and leave switch in the OFF position.

Ensure that electrical supply cables, circuit breakers and other electrical installation equipment are correctly sized for the 12 Amp rating of the unit.

Electrical
Supply
Cable



Make electrical connections to the side of the control box using the plug-in connectors:

6-way connector – Heat Exchanger Section


2-way connector – Pressure Switch

9-way connector – Extract Fan Section



Remove the lid of the control box to access electrical connections within the control box.


Feed the 3-core electrical supply cable for the Extract Fan through the 16mm cable gland, see adjacent picture.



Connect cables from the Extract Fan as shown in the picture:

- Brown live wire – Terminal L_E
- Blue neutral wire – Terminal N
- Green/Yellow wire – Terminal E

See Wiring Diagram 1 for details.




Wire 5 core cable from the Smoke Extract unit located on the duct to terminals E, N, L, S1, S2 in the electric box.

The Supply Fan is pre-wired at the factory to the electric box and will not need any site wiring.

The 16mm size cable gland at the left hand end of the control box, see picture, should be used for wiring the control cables from the site BMS Switch Contacts.

See Wiring Diagram 1 for details.



Recommended wire sizes for electrical connections are as follows:

Electrical Connection	Wire Size
1-phase electrical supply into local isolator on side of unit	1.5mm ² max. for access
24V control cables from Site BMS for Mode and Fan speed	0.75mm ²

COMMISSIONING THE HEAT RECOVERY UNIT

Ensure that the local electrical supply to the Heat Recovery Unit is switched off.

Inspect the outside of the Heat Recovery Unit

Make sure that ductwork is properly fitted to the unit and the correct ducts have been fitted to the correct inlet and outlet spigots on the unit. Check this against Figure 3.

- Fresh Air from Outside (Außenluft) – Duct bringing fresh air from intake louvre in external wall.
- Supply Air to Store (Zuluft) – Duct feeding supply air to Biddle NOZ25 or CC90V unit(s).
- Extract Air from Store (Abluft) – Duct bringing return air back from supermarket.
- Exhaust air to Outside (Fortluft) – Duct taking exhaust air to outlet louvre in external wall.

Make sure that the electrical power cables and the site BMS control cables have been correctly terminated in the control box on the side of the unit. Check this against Wiring Diagram 1. Check that plug-in connectors are plugged into the control box correctly.

Check the inside of the Heat Recovery Unit

Open all hinged doors to gain access inside the unit to carry out commissioning.


Check that all components inside the Heat Recovery Unit are fitted in place and that all fixing bolts and screws are tight. Check that:

- fan wheels spin freely,
- dampers are closed, they cannot be opened by hand and the rubber gasket seals on damper blades are not damaged,
- air filters are fitted correctly and air direction arrows on air filters are pointing the correct way,
- Differential pressure switches are set correctly, see below:

Make sure the condensate trap is filled with water.

For commissioning disconnect the BMS 9-way connector fitted inside the control box so the unit can operate in test mode, see arrows in picture.

Switch ON the electrical isolator mounted on the side of the Heat Recovery Unit.



To carry out commissioning tests all the doors on the unit should be closed, except for the recirculation damper access door in the Supply Fan Section and the Summer By-pass access panel in the Heat Exchanger Section. These should be open to see the dampers operating, see pictures:



Setting Fan Speeds



Refer to graph “k factor = 116”,
Figure 11 for setting fan speeds
using the pressure tapping
readings across the fans

To set the fan speeds 1st
remove the metal cover

see pictures



Set control box switches to Mode 1, Fan Speed III (High) and Test.
Switch ON the electrical isolator on the side of the Heat Recovery Unit.

SETTING SUPPLY FAN SPEEDS

Put pressure gauge across + and – pressure tapings of
Supply Fan

Press Button A once – LED A will flash rapidly

Adjust Supply Fan, High Speed with potentiometer

Set Fan Speed Switch to II (Medium)

Adjust Supply Fan, Medium Speed with potentiometer

Set Fan Speed Switch to I (Low)

Adjust Supply Fan, Low Speed with potentiometer

SETTING EXTRACT FAN SPEEDS

Put pressure gauge across + and – pressure tapings of
Extract Fan

Press Button A once – LED A will flash 3 times every 2
seconds

Adjust Extract Fan, Low Speed with potentiometer


Set Fan Speed Switch to II (Medium)

Adjust Extract Fan, Medium Speed with potentiometer

Set Fan Speed Switch to III (High)

Adjust Extract Fan, High Speed with potentiometer

Press Button A once – LED A will stop flashing



SAVING FAN SPEED SETTINGS


Push Button B (on IQeco Controller) for between 2 and 5 seconds

LED B (on IQeco Controller) will then flash rapidly for 1 second

LED B will then flash once every 3 seconds

LED B will then flash rapidly for 3 seconds – Press Button B during
this 3 second period and fan speed settings are saved into IQeco
Controller

Once the fan speeds have been calibrated refit potentiometer
cover.



k-factor = 116 graph for K3G310-AX54-22 fans in HR3500




FIGURE 11 – SETTING FAN SPEEDS USING PRESSURE TAPPING READINGS

With the BMS 9-way connector still disconnected, set switches on the front of the control panel to TEST, Fan Speed Low and Mode 1.

Switch on the isolator and check that the Fresh Air and Exhaust dampers slowly open. Ensure both the Supply and Extract fans operate at low speed spinning the correct direction (DANGER - BEWARE OF FAN ROTATING). Ensure the Recirculation damper is closed with the larger Summer By-Pass damper open and the small Summer By-Pass damper closed.



Once the position of all dampers has been verified, turn on the Fan Medium Speed Switch and check that both Supply and Extract Fans operate at medium speed. Similarly turn on the Fan High Speed Switch and check that both Fans operate at high speed.

Using the Fan and Mode switches operate the Heat Recovery Unit in Mode 2 and Mode 3. Refer to Page 5 and check that the fans and dampers respond correctly to each Mode selected. Ensure that there is no mechanical noise or vibration from the fans at any speed. Test the three doors switches operate correctly by briefly opening either Supply Fan (x2) or Extract Fan doors and check all fans and dampers have stopped operating.

Site BMS

If all the Modes are operating correctly switch the local isolator OFF. With no Modes or fan speeds selected on the BMS reconnect the BMS 9-way connector and switch the Left Hand TEST/GLT Switch to position GLT (downwards position).

Switch on the isolator and make sure 24V DC is present on terminal FL in the control box and see if there is 24V DC on any of the terminals 1 to 7 (see Wiring Diagram 1, Page 20). If possible, get the Site BMS to test each mode and fan speeds and confirm correct fans and dampers operate.

After checking that the unit is operating correctly, refit Condensate access panel and close the air filter door, making sure safety catches and latches are secured properly.

At the end of the tests ensure the TEST/GLT Switch is left in the GLT position to allow the Site BMS to control the Heat Recovery Unit.

Hand-over to End-User

Before leaving site it is important that there is a 'Hand-Over Meeting' to pass-over the heat recovery system to the end user or their representative. This should include a full and clear explanation of how the system operates with the site BMS and a demonstration showing the heat recovery system running. Be sure to explain that the unit must be serviced annually. See "Servicing the Heat Recovery Unit", Page 26. Explain the operation of the dirty filter light.


Ensure that all instructions and manuals are handed to the end user or their representative.

SERVICING THE HEAT RECOVERY UNIT


Report to the store manager before working on the Heat Recovery Unit. Ensure that the electrical supply to the Heat Recovery Unit is switched off at the local isolator before starting any servicing work.



Remove 2-way plug by pressing the locking clips and pulling plug away from the control box.




Release six clamps and by gripping the handles lift and pull away the access panel away from the Heat Recovery Unit.




Release plate heat exchanger door clamps and open the two doors (see Picture) to access 13mm bolts holding plate heat exchanger sections in place. Beware, doors will swing down to open and are heavy!

Remove 6 x 13mm bolts from the air separator slide plate that hold the three plate heat exchanger sections together.






Pull air separator plate away from the plate heat exchanger sections and slide plate out from the Heat Recovery Unit.



Slide the first plate heat exchanger section out from the unit then slide out remaining plate heat exchanger section(s).

Using a hose pipe clean all plate heat exchangers with water.



Unscrew 2 wing-nuts to release metal clamps at each side of the air filter that hold the air filter inside the unit.

There are two separate air filters in the unit, a fresh air filter type F7 and an extract air filter type G4. See Figure 3 to see where in the unit these two air filters are located.



Remove the dirty air filter from the unit.

We recommend replacing the air filters with a clean new set of filters at every service.

Dirty air filters waste energy. Regular air filter changes are important for the correct performance and energy efficiency of the unit.

For replacement air filters:

x1, Fresh Air Filter HR3500, F7	}	HR3500 FILTER SET Biddle Part No.9C033500
x1, Extract Air Filter HR3500, G4		

Vacuum clean and brush to remove any build-up of dust, dirt and debris within the Heat Recovery Unit, especially on the fans.

Thoroughly clean all metal surfaces inside of the Heat Recovery Unit using warm water, detergent and a cloth.

Note: Fan motors are permanently lubricated and require no additional lubrication.

Clean the condensate drain tray within the unit and check the drain tray spout and condensate pipe drain system is clear by flushing water through from the unit to the drain in the boiler room. Check the condensate drain in the boiler room is not blocked. Make sure the condensate trap is clean and filled with water or condensate may splash within the unit damaging it and leaking out of panels.

Once the Heat Recovery Unit has been cleaned, visually inspect all components and repair or replace if necessary. Check all electrical connections and terminals within the electric box on the side of the unit are tight and that crimp connections have not become loose.

Re-assemble the Heat Recovery Unit by replacing all components in reverse order.

Follow the procedure in Section – Commissioning, Page 21 and fully function test the unit to ensure correct operation.

Fault Finding for the Heat Recovery Unit

If the Heat Recovery Unit does not operate as expected refer to the fault finding table below:

Symptom	Possible Cause	Action Required
Unit does not operate at all	Electrical power is not switched on at the electrical supply or at the local electrical isolator on the side of the Heat Recovery Unit	Switch on electrical power at the electrical supply and the local electrical isolator on the side of the unit
	Door switch(s) is not operating	Check doors are shut and door switch operates correctly
Fan or Damper in Heat Recovery Unit does not operate (switch is in TEST position)	The wrong Mode switch has been operated	Check on Page 5 which fan or damper should operate with the corresponding Mode switch
	Wiring fault inside Electric Box	Refer to separate electric box wiring diagram and rectify fault
	Fault with fan motor, motor capacitor, damper motor or damper	Repair or replace fan, capacitor, damper motor or damper
Fan or Damper in Heat Recovery Unit does not operate correctly (switch is in GLT position)	BMS is not operating	Make sure BMS is switched on and functioning. Check the operation of fans and dampers first with switch in TEST position to ensure fans and dampers all operate correctly.
	The wrong Operating Mode is being called for by the BMS	Check site wiring between the BMS and the Heat Recovery Unit is correct (see Commissioning – Page 21, Site Wiring Diagram - Page 20, Mode explanation - Page 5)
	Wiring fault inside Electric Box	Refer to separate electric box wiring diagram and rectify fault
Airflow is low	Problem with installation:- Ductwork is high resistance – duct too small, bends are too tight, blockages Outside air louvres are high resistance Obstructions in ductwork system	Correct the problem with the bad installation that is making the air resistance too high for the Heat Recovery Unit.
	Fan in NOZ25 or CC90V heater is not operating when the Heat Recovery Unit is operating.	Check the operation of the NOZ25 or CC90V heater and the BMS
	Fresh air intake louvre is blocked by debris	Remove debris from fresh air intake louvre and clean
	Air filters and/or heat exchanger is dirty. See if Dirty Filter Light shows continuously.	Service Heat Recovery Unit as described in Section – Servicing, Pages 26 to 28
	Damper is not opening when it should	Tighten clamp on shaft. Repair or replace damper motor or damper
Heat Recovery Unit sounds noisy	Doors not shut properly	Shut door latches properly
	Defective rubber seal on doors	Repair rubber seal on doors
	Air filters and/or heat exchanger is dirty	Service unit – see Pages 26-28
	Fan has a mechanical fault	Repair fan

If the Heat Recovery Unit system is still not operating correctly call for an approved Biddle service agent.

Warranty

If any problems are encountered with the Heat Recovery Unit please contact your Biddle Service Agent.

Care has been taken in compiling these instructions to ensure they are correct, although Biddle GmbH disclaims all liability for damage resulting from any inaccuracies and/or deficiencies in this documentation. Biddle GmbH retain the right to change the specifications stated in these instructions.

Biddle GmbH
Emil – Hoffmann – Straße 55-59
50996 Köln
Deutschland

Email: info@biddle.de
T: +49 (0)2236 9690-0
F: +49 (0)2236 9690-10
<http://www.biddle.de>

Biddle Air Systems Ltd
St. Mary's Road
Nuneaton
Warwickshire
CV11 5AU
United Kingdom
Telephone: +44 (0)24 7638 4233
Fax: +44 (0)24 7637 3621



EC DECLARATION OF CONFORMITY

as defined by the EC Council Directive on Machinery 2006/42/EC, the Low Voltage Directive 2006/95/EC, Electromagnetic Compatibility Directive 2004/108/EC, the Energy related Products Directive 2009/125/EC

Herewith we declare that the air movement equipment designated below, on the basis of its design and construction in the form brought onto the market by us in accordance with the relevant safety, health and performance requirements of the Machinery.

If alterations are made to the machinery without prior consultations with us, this declaration becomes invalid.

Designation of Equipment : BIDDLE HEAT RECOVERY UNIT

Series Type : HR2500, HR3500

Relevant EC Council Directives : the Machinery Directive (2006/42/EC)
the Low Voltage Directive (2006/95/EC)
the Electromagnetic Compatibility Directive (2004/108/EC)
the Energy related Products Directive (2009/125/EC)

Applied Harmonised Standards : Machinery - EN ISO 14121-1:2007, EN 294:1992, EN 414:2000
LVD - EN 60335-1:2002, EN 60335-2-30:2003, EN 60335-2-40:2003
EMC - EN 61000-6-1:2007, EN 61000-6-3:2007,
EN 61000-3-2:2006 + A2:2009, EN 61000-3-3:2008
ErP - ISO 5801:2007, ISO 12759:2010

Basis of Self Attestation : Quality Assurance to BS EN ISO 9001 : 2008
B.S.I. Registered Firm Certificate Number FM 02234
SGS Test Report DUR 43908/2/R/RG/05
Wemtech Test Report 6660

Responsible Person : Mr. P. Casey, Site Managing Director, Thermoscreens Ltd.

Date : 1st June 2015

Signed :