

Ian Murray

10/07/2026 – 1:28PM

To Robert Riley

In terms of the coastal partners request,  
Measures taken to flood proof the construction.

The construction will be brick and block with solid beam and block concrete floors with encapsulated insulation under screed.

Floor levels will be no lower than existing.

Electrics will be run round at ceiling level and dropped to plugs and light switches minimum 600mm above finished floor level.

Best Regards