

SAFETY, HEALTH AND ENVIRONMENTAL INFORMATION

Please be aware the Client is a duty holder under CDM 2015. By default, the client assumes the duties of the principal designer (PD) until such a time a PD is appointed.

In addition to the hazards/risks normally associated with the types of work detailed on this drawing, note the following significant residual risks. Reference shall also be made to the Designer Risk Assessment ref: 020.5923.DRA

CONSTRUCTION

1. Connection into live Southern Water foul sewer network - appropriate contractor RAMS and Southern Water approvals to be in place prior to commencement of works.

2. Live highway - Contractor to implement appropriate traffic management prior to commencement of works.

3. (Site wide compulsory action) Unknown services - investigation to be undertaken to determine presence of existing services on site prior to commencement of works.

4. (Site wide compulsory action) Unknown ground conditions - intrusive site investigation to be undertaken prior to commencement of works.

MAINTENANCE/CLEANING/OPERATION

No abnormal maintenance/cleaning/operation risks.

USE

No abnormal use risks.

DECOMMISSIONING/DEMOLITION

No abnormal decommissioning/demolition risks.

