

Strategic Planting Schedule

Trees

Abbreviation	Species	Girth	Height	Specification	Qty.
Acer_camp 'Streetwise'	Acer campestre 'Streetwise'	12-14cm	350-400cm	Extra Heavy Standard: 5 brks: 3x: BR/CG: Clear Stem min. 200cm	5 No.
Acer_rub	Acer rubrum	12-14cm	350-400cm	Leader with Laterals: Feathered to base: 4x: BR/CG	1 No.
Amel_lama	Amelanchier lamarckii	10-12cm	300-350cm	Selected Standard: 4 brks: 2x: RB: Clear Stem min. 200cm	3 No.
Betu_pend	Betula pendula	12-14cm	350-400cm	BR/CG; 2x; Selected Standard; clear stem 175-200cm; 4 breaks	3 No.
Cory_colu	Corylus columa	12-14cm	350-400cm	Selected Standard: 4 brks: 2x. BR/CG: Clear Stem 175-200cm	6 No.
Crat_mono	Crataegus monogyna	12-14cm	350-400cm	Selected Standard: 4 brks: 2x: BR/CG: Clear Stem 175-200cm	1 No.
FAG SYL	Fagus sylvatica	14-16cm	400-450cm	1+2: Transplant - seed raised: BR/CG	2 No.
KOEPAFA	Koelreuteria paniculata 'Fastigiata'	12-14cm	350-400cm	BR/CG	7 No.
Lag_indi 'R'	Lagerstroemia indica 'Rosea'	14-16cm	400-450cm	Selected Standard: 4 brks: 2x: BR/CG: Clear Stem 175-200cm	1 No.
Liqu_styr	Liquidambar styraciflua	12-14cm	350-400cm	Selected Standard: 4 brks: 2x: BR/CG: Clear Stem 175-200cm	6 No.
Malu_sylv	Malus sylvestris	10-12cm	300-350cm	BR/CG; 2x; Selected Standard; clear stem 175-200cm; 4 breaks	1 No.
Pinu_pine	Pinus pinea			200-250cm Leader with Laterals; CG	4 No.
Prun_avi	Prunus avium	12-14cm	350-400cm	BR/CG; 2x; Selected Standard; clear stem 175-200cm; 4 breaks	3 No.
Taxo_dist	Taxodium distichum		300-350cm	Leader with Laterals: 5x: RB	1 No.

Native Hedges

Abbreviation	Species	Height	Specification	Density	% Mix	Qty.
Acer_camp	Acer campestre	100-125cm	RB	0.5Ctr Double Staggered at 0.25m offset	15%	113 No.
Cornus_sang	Cornus sanguinea	100-125cm	RB	0.5Ctr Double Staggered at 0.25m offset	10%	77 No.
Cory_avel	Corylus avellana	100-125cm	RB	0.5Ctr Double Staggered at 0.25m offset	15%	113 No.
Crat_mono	Crataegus monogyna	100-125cm	RB	0.5Ctr Double Staggered at 0.25m offset	15%	113 No.
Ilex_aqui	Ilex aquifolium	100-125cm	RB	0.5Ctr Double Staggered at 0.25m offset	10%	77 No.
Ligu_vulg	Ligustrum vulgare	100-125cm	RB	0.5Ctr Double Staggered at 0.25m offset	5%	39 No.
Malu_sylv	Malus sylvestris	100-125cm	RB	0.5Ctr Double Staggered at 0.25m offset	15%	113 No.
Prun_spin	Prunus spinosa	100-125cm	RB	0.5Ctr Double Staggered at 0.25m offset	5%	39 No.
Rosa_cani	Rosa canina	100-125cm	RB	0.5Ctr Double Staggered at 0.25m offset	5%	39 No.
Vibu_opul	Viburnum opulus	80-120cm	BR Transplant	0.5Ctr Double Staggered at 0.25m offset	5%	39 No.

Clipped Hedges

Abbreviation	Species	Height	Pot Size	Specification	Density	Qty.
Esca 'A.B'	Escallonia 'Apple Blossom'	40-60cm	3L	Bushy: 4 brks: C	3/m	63 No.
Ligu_vulg	Ligustrum vulgare	80-100cm	10L	Bushy: 9 brks: C	3/m	315 No.
Phot_fras 'RR'	Photinia x fraseri 'Red Robin'	40-60cm	5L	Branched: 6 brks: C	3/m	48 No.

0m 10m 20m

north

- All dimensions in millimetres unless otherwise indicated. All levels in metres relative to Ordnance Datum and are positive (AOD) unless otherwise indicated.
- Figure dimensions only to be taken from this drawing, do not scale except for planning purposes. Dimensions to be checked on site.
- For civil and structural matters including existing and proposed services, sub-base construction and site structures (including retaining walls over 900mm height) refer to information by others.
- The original version of this drawing was produced in colour - monochrome copies should not be relied upon to accurately reflect all drawing elements.

Conversion boundary

Site boundary (Site-wide landscape scheme)

Buildings to be retained

Areas where hardstanding needs to be carefully broken out

Existing trees & vegetation

Existing tree to be retained and protected in accordance with the arboricultural report.

Root Protection Area - refer to arboricultural report. To remain undisturbed and uncompacted (no material or equipment storage permitted)

Retained, extended and enhanced understorey planting. Rhododendrons and laurels to be removed and replaced with native mix in accordance with ecologists report.

Soft landscape

Reinforcement to the existing boundary vegetation with a native hedge mix, where appropriate

Specimen tree

Private rear gardens - fenced & laid to turf. Sheds where shown. For details of bin and bicycle stores etc. refer to architect's plans.

Ornamental shrubs & groundcover

Clipped hedge

Mixed native hedge

Native buffer planting

Mown amenity grass

Species rich grass

Bulbs

Marginal / emergent planting to pond

Climbers to porch columns

rev.	date	by	chk	notes
P06	05.03.25	MS	MH	Tree T511 reincorporated
P05	07.02.25	PS	MH	Base updated with cycle path
P04	18.09.24	MH	-	Alignment of link to northern cycle route altered
P03	24.01.24	MH	-	Existing tree T511 removed
P02	19.01.24	EB	MH	Updated site layout for cycle/ pedestrian route
P01	06.12.23	MH	MH	First issue - Based on 2237-TF-XX-00-DR-L-1001, without conversion area boundary shown

project	Southleigh Park House
title	General Arrangement- with Strategic Landscape Planting
status	Planning
scale @ A1	1:500
dwg no	2237-TF-XX-00-DR-L-1003
references	BARG230130_SL01_L

terrafirma LANDSCAPE ARCHITECTS
Suite B, Ideal House, Bedford Road, Petersfield, Hampshire GU32 3QA
Tel: +44 (0)1730 262 040
Web: www.terrafirmaconsultancy.com
©Copyright reserved 2025