

Tree Protection During the Proposed Works

The existing trees will be retained and protected throughout the installation of the proposed garden fence.

Care will be taken to avoid unnecessary disturbance to the ground surrounding the existing trees. No construction materials, excavated material, machinery or equipment will be stored within the immediate vicinity of the trees.

Where fence posts are required close to existing trees, post locations will be carefully selected to minimise disturbance to existing roots. Excavation will be undertaken carefully by hand where necessary, and significant roots encountered during the works will not be severed or damaged. Where a root conflict is identified, the position of the fence post will be adjusted where practicable to avoid the root.

No mechanical excavation will take place close to the trees where this could result in damage to roots. Existing ground levels around the trees will be maintained, and no additional soil or construction material will be placed around the base of the trees.

The trees, including their trunks, branches and surrounding rooting areas, will be protected from accidental damage for the duration of the works. The proposed fence installation will be carried out using low-impact working methods with the intention of retaining and protecting the existing trees.

NOTE: This is not a Tree Report this outlines the way in which the trees will be protected during works.

BELL VISION STUDIO

Architectural designers
Contact Number: 07293 370 774
Email: Joshua@bellvisionstudio.com

www.bellvisionstudio.com

Client:

Gemma Cowan

Notes:

1. ALL LEVELS AND DIMENSIONS TO BE CHECKED ON SITE.

2. THIS DRAWING TO BE READ IN CONJUNCTION WITH SPECIFICATIONS & ALL OTHER CONSULTANTS DRAWINGS.

3. ALL DIMENSIONS AND LEVELS ARE TO BE VERIFIED ON SITE BY THE CONTRACTOR BEFORE COMMENCING ANY WORK.

Project:

**Fence Planning - 59
Longwood Ave**

Title:

TREE PROTECTION

Scale:	NTS
Drawn By:	JB
Approved:	N/A
Date Drawn:	06/08/26
Revisions:	Rev A

007