




**Land east of St. Patrick's RC Church,
Hayling Island PO11 0QU**

**Drainage Strategy Report dated August
2026**

Land east of St. Patrick's RC Church, Hayling Island PO11 0QU

Drainage Strategy Report dated August 2026

1.0 Background Information

- 1.1 The site known as ' Land east of St. Patrick's RC Church, Hayling Island PO11 0QU ' is shown by the location plan & Google map image included within Appendix A.
- 1.2 The land within the site boundary currently consists of vacant land as shown by the google image included within Appendix A and the existing site layout plan within Appendix C.
- 1.3 Planning consent is being sought for the construction of 2 no. residential units and associated hardstanding areas; as shown by the architectural site plan included within Appendix D.
- 1.4 This drainage strategy has been formed in accordance with the requirements of the Flood & Water Management Template included within Appendix I.

2.0 Site Topography

- 2.1 The topographical survey, included within Appendix B, is generally flat with an average level of 5.50m AOD.
- 2.2 There is a slight depression on the site.
- 2.3 There is also a small bank to the northern boundary of the site; as shown by the topographical survey.
- 2.4 The site is currently covered by grass.

3.0 Prevailing Ground Conditions

- 3.1 The site investigation report included within Appendix F identifies the prevailing ground condition to be:-
 - Made Ground over River Terrace Deposits over London Clay Formation

- 3.2 Section no. 3.2 of the site investigation report shows the results of infiltration testing. These results show that the use of soakaways for the disposal of surface water run off is not feasible on this site.

4.0 Sensitivity of Discharge Points

- 4.1 The Code of Practice for Sustainable Drainage Systems provides a flexible approach to drainage systems with a wide range of components and includes a hierarchy of techniques. These are:-
1. Prevention - The use of good site design and housekeeping measures on site to prevent run-off and pollution.
 2. Source Control - Control of run off at or very near to its source.
 3. Site Control - Management of water from several sub catchment areas.
 4. Regional Control - Management of run off from several sites, typically in a detention pond or wetland.
- 4.2 With the above in mind surface water disposal will respect the hierarchy of techniques outlined above.
- 4.3 Source control is to be introduced in the following ways:-
- Surface water will be discharged to the public foul sewer due to the lack of ditches or surface water sewers near or adjacent to the site.
- 4.4 Rainfall within soft landscaped areas will be allowed to permeate through the ground in order to mimic as closely as possible the natural drainage from the site before development.

5.0 Existing Surface Water Flows

- 5.1 The site is a greenfield site with no formal drainage provision.
- 5.2 The site layout drawings, included within Appendices D & E, show that the extent of impermeable roofs and hardstanding areas for the redeveloped site is to be:-

Building Areas	246 m ²
Hardstanding & Path Areas	270 m ²

6.0 Existing Drainage Network

- 6.1 The site is currently laid out with grass. There is no surface water drainage provision on the site.

7.0 Failures of the Existing Drainage Regime

- 7.1 There are no records of failures of the existing drainage regime.

8.0 Proposed Drainage Patterns

- 8.1 The drawing, included within Appendix D, show that the site is to be laid out with impermeable hardstanding and roof areas with surface water patterns following existing ground levels.
- 8.2 The proposed surface water drainage design, shown by the drawing within Appendix I, includes for an attenuation tank and hydrobreak as shown on the drainage drawing, with sufficient attenuation storage to contain the 1 in 100 year storm with a 45% climate change allowance with a restricted flow of 0.7 l/s to the existing foul sewer.

9.0 Surface Water Treatment

- 9.1 Surface water treatment is to be achieved, in accordance with Ciria SuDS Manual C753, with a catchpit installed to catch silt deposits prior to discharge of attenuation tanks.

10.0 Surface Water Drainage Calculations

- 10.1 The stormwater calculations, included within Appendix J, allow sufficient storage of 39.3m³ to be provided for the proposed attenuation tanks to accept the 1 in 100 year storm with 45% climate change allowance during periods of high rainfall. The surface water drainage calculations assume an attenuated flow of 0.7 l/s via a hydrobreak to the public foul sewer. The connection to the existing foul sewer will be the subject of a section 106 agreement with Southern Water.

11.0 Run off Exceedance Design Criteria

- 11.1 The run off exceedance design criteria has been considered and hardstanding areas will be formed with falls as per the existing ground levels. Building finished floor levels will be set at sufficient height to ensure that the buildings are not at risk from run off in times of exceedance.

12.0 Maintenance Regimes

- 12.1 A management company will be set up for the development with responsibility for the maintenance of drainage elements within common areas. The property owners will be responsible for the maintenance of drainage elements within their ownership boundaries.
- 12.2 The inspection chamber directly upstream of the attenuation tank will be formed as a catchpit manhole. Manholes will be inspected by the management company on an annual basis and cleaned out to remove silt. Individual householders will be responsible for the maintenance of drainage elements within their property boundary.
- 12.2 The management company will be responsible for the maintenance of all common areas of the site including external areas and on-site foul and surface water drainage.

13.0 Urban Creep

- 13.1 The drainage calculations, included within Appendix J, do not take account of urban creep as the site is to be developed to its full extent with no scope for expansion.

14.0 Construction Phase

- 14.1 The access road and associated drainage elements will be installed as the first phase of the development to deal with surface water run off during the construction period.

15.0 Foul Drainage

- 15.1 The proposed foul drainage discharges will be connected to the public sewer as shown by the drainage layout plan included within Appendix I. This connection will be the subject of a section 106 agreement with the water authority.

Appendix A

**Location Plan
Google Image**





Russells.kitchen



Camp site shop



Cemetery



St. Patrick's Church



A3023


Manor Rd

Appendix B

Topographical Survey

Appendix C

Existing Site Layout Plan



Note:
Drawing to be read in conjunction with
Proposed Site Plan, Tree Report by
Arbiculturalist and BGN Report

DRAWING REFERENCE
608 PLO2

REVISION
A

SCALE
@A3

PROJECT:
Land to East of St Patricks RC Church, Manor Road

DRAWING
SITE PLAN: EXISTING

Appendix D

Proposed Site Layout Plan



Schedule of Accommodation:


Bungalow 1. 3 bedroom GIA 128m²
Bungalow 2. 3 bedroom GIA 118m²

Note:
Drawing to be read in conjunction with:
Proposed Site Plan
Tree Report
BGN Report
Flood Risk Assessment


Appendix E

Architectural Layouts


Bungalow 1.




FLOOR PLAN
1:100




ROOF PLAN
1:100







FRONT (NW) ELEVATION
1:100




ENTRANCE (SW) ELEVATION
1:100



REAR (SE) ELEVATION
1:100



SIDE (NE) ELEVATION
1:100



SECTION
1:100

SCHEDULE OF MATERIALS

- 1 Roof- Slate tiles, black;
- 2 Walls- Render, white;
- 3 Cladding- Vertical boarding to gables and canopy, black;
- 4 Windows and doors- Powder coated aluminium, black
- 5 Window surround (front)- Powder coated aluminium, black
- 6 Box gutter/leaves- Powder coated aluminium, black;




SCALE 1:100


0m

5m


Bungalow 2.




FLOOR PLAN
1:100




ROOF PLAN
1:100







FRONT (NW) ELEVATION
1:100




SIDE (SW) ELEVATION
1:100



REAR (SE) ELEVATION
1:100



ENTRANCE (NE) ELEVATION
1:100



SECTION
1:100

SCHEDULE OF MATERIALS

- 1 Roof- Slate tiles, black;
- 2 Walls- Render, white;
- 3 Cladding- Vertical boarding to gables and canopy, black;
- 4 Windows and doors- Powder coated aluminium, black
- 5 Window surround (front)- Powder coated aluminium, black
- 6 Box gutter/leaves- Powder coated aluminium, black;



SCALE 1:100



Appendix F
Site Investigation Report



Ground Investigation Report

at

**Land east of St Patrick's RC Church, Hayling Island, Hampshire,
PO11 0QU**

for

Billet Homes Ltd

**Reference: 22440/GIR Rev I.0
July 2026**

Control Document

Project

Land east of St Patrick's RC Church, Hayling Island, Hampshire PO11 0QU

Document Type

Ground Investigation Report

Document Reference

22440/GIR Rev 1.0

Document Status

Final

Date

July 2026

Prepared by

A R Nair BSc MSc FGS
(an@soilslimited.co.uk)

First check by

Eur Ing R B Higginson BSc, PGDip, CEng, MICE, FGS

Second check by

C Morrison BSc (Hons), FGS, MEnvSc

This is not a valid document for use in the design of the project unless it is titled Final in the document status box.

Current regulations and good practice were used in the preparation of this report. The recommendations given in this report must be reviewed by an appropriately qualified person at the time of preparation of the scheme design to ensure that any recommendations given remain valid in light of changes in regulation and practice, or additional information obtained regarding the site.



Commission

This document comprises the Ground Investigation Report (GIR) and incorporates the results, discussion, and conclusions to intrusive works and laboratory testing.

Commission Record	
Client	Billet Homes Ltd
Site Name	Land east of St Patrick's RC Church, Hayling Island, Hampshire PO11 0QU
Grid Reference	SU 718 005
Soils Limited Quotation Ref	Q31302rev3, dated 13 th May 2026
Signed Order Form	Q31302rev3, dated 14 th May 2026

The record of revision to this document is presented below:

Record Of Revisions		
Revision	Date	Reason
1.0	July 2026	Original to the Client

Note(s): The latest revised document supersedes all previous revisions of the GIR produced by Soils Limited.

Documents associated with this development that must be referred to are given below.

Record Of Associated Documents			
Reference	Type	Date	Creator
608 PLO3	Site Plan -Proposed	July 2026	Lilley Architecture

Limitations and Disclaimers

The report was prepared solely for the brief described in our quotation and Section 1.1 of this report. We disclaim any responsibility to the Client and others in respect of any matters outside the scope of our engagement.

We have exercised all reasonable skill, care and diligence within the terms of the Contract with the Client, incorporation of our General Conditions of Contract of Business and considering the resources devoted to us by agreement with the Client.

This report is a snapshot of the site and conditions taken only at the time of our investigation works and described in our reporting. The ground is a product of continuing natural and artificial processes and has variation by depth and location that cannot be determined absolutely. While a ground investigation will aim to understand and mitigate, risk cannot be eliminated.

Current regulations and good practice were used in the preparation of this report. Consideration of any subsequent changes to regulations or practice that may have occurred following issue of this report is the responsibility of the user.

If the term "competent person" is used in this report or any Soils Limited document, it means an engineering geologist or civil engineer with a minimum of three years post graduate experience in the understanding and application of the appropriate codes of practice.

Unless the site investigation works have been designed and specified in accordance with EC7, this report is not a Ground Investigation Report as defined by Eurocode 7.

Any reference to ground level relates to the site level at the time of the investigation, unless otherwise stated. Ground elevations and coordinates are only provided when this forms part of our engagement.

A survey of the possible presence or absence of invasive species including Japanese Knotweed is outside the scope of this investigation.

Copyright of all printed material including reports, survey data, drawings, laboratory test results, trial pit and borehole log sheets remains with Soils Limited.

Unless specifically granted, in writing, by Soils Limited, no parties other than the named client hold reliance or license over this report. The Client may not assign the benefit of the report or any part to any third party without the written consent of Soils Limited. Use of this report by others is wholly at their own risk.

License for and reliance on this report is only valid once we have been paid in full for this engagement. In the event of non-payment, we reserve the right to notify parties other than the client of failure to pay and our cancellation of license and reliance.

Contents

Commission	i
Limitations and Disclaimers.....	i
Section 1 Introduction	1
1.1 Objective of Investigation	1
1.2 Site Description.....	1
1.3 Proposed Development	1
1.4 Anticipated Geology	1
1.4.1 River Terrace Deposits	1
1.4.2 London Clay Formation.....	2
Section 2 Site Works	3
2.1 Project Works	3
2.2 Ground Conditions	3
2.3 Established Ground Conditions.....	4
2.4 Roots	4
2.5 Groundwater	5
Section 3 In-Situ and Laboratory Testing.....	6
3.1 Standard Penetration Tests	6
3.2 Infiltration Tests	6
3.3 Atterberg Limit Tests and Moisture Content Determinations	6
3.4 Sulphate and pH Tests	7
3.5 Radon	7
Section 4 Foundation Scheme	8
4.1 Foundation Recommendations	8
4.2 Piled Foundations	8
4.3 Subsurface Concrete	9
4.4 Excavations	9

List of Figures

Figure 1 – Site Location Map	11
Figure 2 – Aerial Photograph	12
Figure 3 – Exploratory Hole Plan	13

List of Tables

Table 2.1 Final Depth of Exploratory Holes.....	3
Table 2.2 Ground Conditions	4
Table 2.3 Established Depth of Root Penetration	4
Table 3.1 Hammer Efficiency	6
Table 3.2 Standard Penetration Tests (SPT) Interpretation	6
Table 3.3 Infiltration Rates	6
Table 3.4 Atterberg Limit Results Classification	7
Table 3.6 Sulphate and pH Test Results.....	7
Table 4.1 Concrete Classification.....	9

List of Appendices

Appendix A Standards and Resources

Appendix B Field Work

Appendix B.1 Engineers Logs

Appendix C Geotechnical In-Situ and Laboratory Testing

Appendix C.1 Interpretation

Appendix C.2 Geotechnical In-Situ and Laboratory Results

Appendix D Preliminary Pile Design

Appendix E Information Provided by the Client

Section I Introduction

1.1 Objective of Investigation

The Client commissioned Soils Limited to undertake an intrusive ground investigation and to prepare a Ground Investigation Report to supply the Client and their designers with information regarding ground conditions, to assist in preparing a foundation scheme for development that was appropriate to the settings present on the site.

The investigation was to be made by means of in-situ, geotechnical laboratory testing undertaken on soil samples taken from the exploratory holes.

No preliminary investigation or contamination testing was part of the scope of this investigation.

1.2 Site Description

At the time of investigation in June 2026, the site was an unused land located to the south of Manor Road, predominantly covered in gravel and grass and with no structures.

Two trees were located just beyond the north-eastern boundary of the site. The site was relatively flat and was bounded by a cemetery to the west, Manor Road to the north, residential buildings to the east, and a campsite to the south.

A site location plan is given in Figure 1. An aerial photograph of the site and its close environs has been included in Figure 2.

1.3 Proposed Development

The development proposals comprise the construction of two new bungalows with private gardens, a driveway with hard landscaping, and a new access road via Manor Road.

This report relies on the items listed in the Record Of Associated Documents and recommendations apply only to this scheme. Any changes require consultation with Soils Limited. Development plans are in Appendix E.

1.4 Anticipated Geology

The 1:50,000 BGS map showed the site to be located on the bedrock London Clay Formation with overlying superficial deposits of River Terrace Deposits.

1.4.1 River Terrace Deposits

The rivers Test and Itchen have deposited extensive spreads of River Terrace Deposits in the Southampton area, representative of ancient floodplains. In total, eleven terraces have been recorded. The River Terrace Deposits consist predominantly of gravels made up of subangular to subrounded flints with a significant sand component locally with lenses of silt, clay or peat.

The five highest terraces have appreciable clay content. Poorly sorted, clayey and sandy silts and silty clays overlie the 1st, 3rd, 5th and 6th terraces and locally at above terrace gravels

1.4.2 London Clay Formation

The London Clay Formation in the Hampshire region comprises silty and sandy clay, clayey and sandy silt, silty sand; sporadic claystones and thin beds of flint pebbles. The formation includes the Bognor Sand, Whitecliff Sand, Durley Sand, Portsmouth Sand and Nursling Sand Members. Crystals of gypsum (Selenite) are often found within the weathered part of the London Clay, and precautions against sulphate attack to concrete are sometimes required.

The lowest part of the London Clay Formation rests on the Reading Formation (Lambeth Group).

Section 2 Site Works

2.1 Project Works

The project works were undertaken on 1st and 2nd June 2026, with subsequent sample logging, laboratory testing, and reporting. The works comprised:

- Scanning exploratory holes with a cable avoidance tool (CAT & Genny)
- 3No machine-excavated trial pits to depths ranging between 1.00m and 2.05m bgl
- 2No infiltration tests in TPSK1 and TSPK2 in accordance with BRE DG:2016
- 1No 15.00m deep cable percussive borehole with SPTs at every 1.00m to 5.00m and every 1.50m thereafter
- 10.00m deep groundwater monitoring standpipe
- Geotechnical laboratory testing

Figure 2 shows exploratory hole locations.

Soil cores were logged and sub-sampled for laboratory analysis.

The cable percussive borehole BH1 was backfilled using gravel and bentonite following the installation, and trial pits were backfilled using arisings, compacted in layers and any excess left mounded for future settlement.

2.2 Ground Conditions

The maximum depths of exploratory holes are given in Table 2.1. The depths presented were measured from ground level at the time of the investigation.

Table 2.1 Final Depth of Exploratory Holes

Exploratory Hole	Depth (m bgl)	Exploratory Hole	Depth (m bgl)
TPSK1	1.00	TP3	2.00
TPSK2	2.05	BH1 ^W	15.00

Note(s): ^W - well installation. The depths given taken from the ground level adjacent to each exploratory hole the time of investigation.

Soils are classified as Topsoil if they contain organic material or result from natural weathering. Where soils have been altered by human activity or contain over 5% non-natural material, they are labelled as Made Ground.

For full details, see Appendix B. For discussion, the soil conditions found in the exploratory holes, from top to bottom, are summarised as follows:

Made Ground/Topsoil (MG/TS)
River Terrace Deposits (RTD)
London Clay Formation (LCF)

The ground conditions are summarised in Table 2.2.

Table 2.2 Ground Conditions

Strata	Depth Encountered (m bgl)		Typical Thickness (m)	Typical Description
	Top	Bottom		
MG	0.00	0.30-0.35	0.33	Yellowish brown sandy gravelly SILT with flint and occasional brick
RTD	0.30-0.35	1.00 ¹ -4.00	3.70	Firm yellowish brown /Orangish brown sandy gravelly CLAY
LCF	4.00	15.00 ¹ +	Not proven	Stiff dark grey CLAY

Note(s): ¹ Final depth of exploratory hole. ² Base of strata not encountered. The depths given were taken from the ground level adjacent to each exploratory hole at the time of investigation.

2.3 Established Ground Conditions

The Made ground was found to generally extend to 0.30-0.35m bgl followed by River Terrace Deposits to a maximum depth of 4.00m bgl, which was encountered within BH1. The high blow counts obtained within the River Terrace Deposits were due to the presence of flint gravels while undertaking the SPTs. The London Clay Formation was only encountered within BH1 from a depth of 4.00m bgl and persisted to the maximum investigatory depth of 15.00m bgl.

2.4 Roots

Roots (including rootlets) were noted in the recovered samples to the depths shown in Table 2.3.

Table 2.3 Established Depth of Root Penetration

Exploratory Hole	Depth (m bgl)	Exploratory Hole	Depth (m bgl)
TPSK1	1.00	TP3	1.10
TPSK2	1.10	BH1	4.00

Note(s): The depths given taken from the ground level adjacent to each exploratory hole the time of investigation.

Roots were recorded on cable percussive borehole logs, based on observations from the soil cores. Cable percussive borehole sampling can identify the presence of roots at depth but provides localised information only. Trial pits allow broader visual assessment of root distribution, orientation and condition. Logging the faces of a supported excavation would give more information than can be obtained from arisings.

Google Earth analysis indicates that two trees have been present along the north-eastern boundary of the site since 1999. These trees were located within the neighbouring residential property and were present at the time of the investigation.

2.5 Groundwater

Groundwater was not encountered in any exploratory holes. Groundwater levels vary seasonally, typically rising from September's low to March's high. Determining equilibrium conditions requires multiple observations via groundwater monitoring wells over an extended period of time.

A 50mm standpipe was installed within BH1 to allow for future monitoring of groundwater levels, should this be required. However, groundwater monitoring was not included within the scope of this investigation, and no monitoring visits have been undertaken to date.

Section 3 In-Situ and Laboratory Testing

3.1 Standard Penetration Tests

Standard Penetration Tests (SPTs) were undertaken in BH1. The results were interpreted based on the classifications outlined in **Error! Reference source not found..**

Table 3.1 Hammer Efficiency

SPT Hammer Ref	Energy Ratio Er (%)
AR 3552	67

Table 3.2 Standard Penetration Tests (SPT) Interpretation

Strata	Depth Range (m bgl)	N60 Range	Soil Classification	Inferred Cu (kPa)
RTD	0.00-4.00	9-49	Medium to Very High	45-245
LCF	4.00-15.00+	11-35	Medium to High	55 – 155

A full interpretation of the SPT results is outlined in **Error! Reference source not found..**

3.2 Infiltration Tests

Infiltration testing was undertaken in TPSK1 and TPSK2 within the River Terrace Deposits following the principles of BRE Digest 365 Soakaway design: 2016

The water level within TPSK1 decreased by only 24 cm during the 432-minute testing period. In contrast, the water level within TPSK2 remained unchanged throughout the 409-minute testing period. BRE 365 compliance was not achieved within any of the pits.

Table 3.3 Infiltration Rates

Exploratory Hole	Test No.	Infiltration Rate (m/s)	Comment
TPSK1	1	NA	Insufficient head loss to calculate an
TPSK2	1	NA	infiltration rate

3.3 Atterberg Limit Tests and Moisture Content Determinations

A summary is given in Table 3.3 of the Atterberg Limit tests and Moisture Content determinations made on three samples, one obtained from the River Terrace Deposits and the remaining two from the London Clay Formation. The results were classified for volume change potential in accordance with BRE Digest 240 and NHBC Standards Chapter 4.2.

Table 3.4 Atterberg Limit Results Classification

Stratum	M/C (%)	PI (%)	>425µm (%)	Mod PI (%)	Class	VCP	
						NHBC	BRE
RTD	20-21	28-38	79-100	25-38	CI – CH	Medium	Medium
LCF	25-29	37-53	100	37-53	CH-CV	Medium to High	Medium to High

Note(s): BRE Volume Change Potential refers to BRE Digest 240 (based on Atterberg results). VCP=Volume Change Potential. Modified PI corrected for % retained on 425µm sieve. NHBC Volume Change Potential refers to NHBC Standards Chapter 4.2 Soils Classification based on British Soil Classification System. The Atterberg Limit Tests were undertaken in accordance with BS 1377:Part 2:1990 Clauses 3.2, 4.3 and 5

Laboratory test certificates are presented in Appendix C.1.

3.4 Sulphate and pH Tests

Water soluble sulphate (2:1) and pH testing in accordance with Building Research Establishment Special Digest 1, 2005, 'Concrete in Aggressive Ground' was undertaken on two soil samples obtained from the River Terrace Deposits and the remaining one from the London Clay Formation.

Table 3.5 Sulphate and pH Test Results

Strata	Depth (m bgl)	Sulphate Concentration (mg/l)	pH
RTD	1.50-3.00	50-150	8.2-8.4
LCF	6.00	340	8.3

The significance of the sulphate and pH test results are discussed in Section 4.3 and the laboratory test certificated presented in Appendix C.1.

3.5 Radon

Radon is a naturally occurring radioactive gas that comes from the decay of uranium in rocks and soil. In the UK, radon levels vary by region, with higher concentrations typically found in areas with granite or other uranium-rich geology, such as parts of Cornwall, Devon, the Peak District, and some areas of Wales and Scotland, however Radon Affected Areas are present in wide areas across the UK.

The UKHSA-BGS digital Indicative Atlas of Radon in the United Kingdom shows the site was situated within a 1km grid square where 3-5% of properties are above the action level for radon. This **indicates** that basic radon protective measures will likely be required within the proposed development.

The designer must obtain a site-specific Radon report from UKRadon.org and follow the guidance obtained from both the report, the Building Regulations Approved Document C and the Local Authority. Occupied basement and cellar areas are at additional risk from radon even if outside a radon affected area so further advice must be sought where these are proposed.

Section 4 Foundation Scheme

4.1 Foundation Recommendations

Foundations **must not** be constructed within any Made Ground and due to the likely variability and potential for large load-induced settlements both total and differential.

According to NHBC Standards Chapter 4.2 'Building near trees', soils of the River Terrace Deposits were classified as being of MEDIUM volume change potential (VCP) and the soils of the London Clay Formation were classified as Medium to High volume change potential.

It is understood that the client is considering a piled foundation solution, which is considered appropriate given the ground conditions encountered.

4.2 Piled Foundations

The piled foundations must be taken through any Made Ground and River Terrace Deposits into suitable strength soils of the London Clay Formation.

The construction of a piled foundation is a specialist job with the actual pile working load depending on the pile type and installation method. Prior to finalising the foundation design the advice from a reputable contractor who is familiar with the ground and groundwater conditions present at the site must be sought.

The vertical load capacities are provided for varying diameters and lengths of bored piles taken into the London Clay Formation, based on geotechnical laboratory testing and in-situ test and must only be used for preliminary design purposes.

A factor of safety of 3 was applied to the characteristic line derived from testing undertaken, for both the shaft and base load capacities.

The bearing values given in Appendix D., are applicable to single vertically loaded piles. Where piles are to be constructed in groups the bearing value of each individual pile should be reduced by a factor of about 0.8 and a calculation made to check the factor of safety against block failure.

An adhesion value (α) of 0.45 was used to calculate the skin friction and a bearing capacity factor (N_c) of 9 was adopted for the cohesive bands of the London Clay Formation.

From ground level the upper 4m of the pile shaft has been ignored in the preliminary pile design given.

To prevent necking of the green concrete, temporary casing may be required where the pile passes through the Made Ground, River Terrace Deposits or London Clay Formation and below the groundwater table (if encountered). To achieve the full bearing value a pile should penetrate the bearing stratum by at least five times the pile diameter.

No allowance has been made for negative skin friction that could be generated where piles pass through Made Ground and very soft cohesive and / or organic soils deposits underlying the site. The negative skin friction must be applied to the pile working load and must not be factored.

Guidance on the design of a working platform for piling rigs can be provided by Soils Limited in accordance with the BRE "Working platform for tracked plant, 2004" documentation.

If a piled foundation scheme is to be adopted for the proposed development, to prevent any downward migration of contaminants into the underlying groundwater/aquifers or create preferential vertical pathways between aquifers, specific piling techniques should be employed in accordance with The National Groundwater and Contaminated Land Centre Report NC/99/73: Piling and Penetrative Ground Improvement Methods on Land Affected by Contamination: Guidance on Pollution Prevention published by the EA, which presents guidance on piling on contaminated sites.

4.3 Subsurface Concrete

The sulphate and pH tests carried out in accordance with BRE Special Digest 1, 2005, 'Concrete in Aggressive Ground', established the site concrete classifications for each stratum as presented in Table 4.1.

Table 4.1 Concrete Classification

Stratum	Design Sulphate Class	ACEC Class
RTD	DS-I	AC-Is
LCF	DS-I	AC-Is

Concrete to be placed in contact with soil or groundwater must be designed in accordance with the recommendations of Building Research Establishment Special Digest 1 2005, 'Concrete in Aggressive Ground' considering any possible exposure of potentially pyrite bearing natural ground and the pH of the soils.

4.4 Excavations

Shallow excavations in the Made Ground/Topsoil and River Terrace Deposits are likely to be at best marginally stable in both the short and long term.

Deeper excavations and those taken below the groundwater table into the London Clay Formation are likely to be unstable and require support. Unsupported earth faces formed during excavation may be liable to collapse without warning and suitable safety precautions must therefore be taken to ensure that such earth faces are adequately supported or battered back to a safe angle of repose.

Excavations beneath the groundwater table are likely to be unstable and allowance made for shoring and dewatering of both foundation and utilities trenches.

List of Figures

Figure 1 – Site Location Map	11
Figure 2 – Aerial Photograph	12
Figure 3 – Exploratory Hole Plan	13

List of Appendices

Appendix A Standards and Resources

Appendix B Field Work

Appendix B.1 Engineers Logs

Appendix C Geotechnical In-Situ and Laboratory Testing

Appendix C.1 Interpretation

Appendix C.2 Geotechnical In-Situ and Laboratory Results

Appendix D Preliminary Pile Design

Appendix E Information Provided by the Client



Figure 1 – Site Location Map

Job Number
22440

Project
Land east of St Patrick's RC Church, Hayling Island,
Hampshire, PO11 0QU

Client
Billett Homes Ltd

Date
July 2026



Figure 2 – Aerial Photograph

Job Number
22440

Project
Land east of St Patrick's RC Church, Hayling Island, Hampshire, PO11 0QU

Client
Billett Homes Ltd

Date
July 2026



Figure 3 – Exploratory Hole Plan

Job Number
22440

Project
Land east of St Patrick's RC Church, Hayling Island, Hampshire, PO11 0QU

Client
Billett Homes Ltd

Date
July 2026

Appendix A Standards and Resources

The site works, soil descriptions and testing were undertaken in accordance with the following standards where applicable:

- BS 5930:2015+A1:2020 and BS EN ISO 22476-2 2005+A1:2011
- BS 5930:2015+A1:2020 and BS EN ISO 22476-2&3:2005+A1:2011
- BS 5930:2015+A1:2020 and BS EN ISO 22476-3:2005+A1:2011
- BS EN 1997-1:2004+A1:2013 Eurocode 7. Geotechnical design
- BS EN ISO 14688-1:2018 - Geotechnical investigation and testing - Identification and description
- BS EN ISO 14688-2:2018 - Geotechnical investigation and testing - Principles for a classification
- BS 8004:2015 – Code of practice for foundations
- BS 1377:1990 Parts 1 to 8
- BRE Digest 241 “Low-rise buildings on shrinkable clay soils: Part 2
- BRE Special Digest 1, 2005, ‘Concrete in Aggressive Ground’
- Stroud, M. A. 1974, “The Standard Penetration Test – its application and interpretation”, Proc. ICE Conf. on Penetration Testing in the UK, Birmingham. Thomas Telford, London.
- N.E. Simons, B.K. Menzies, “A Short Course in Foundation Engineering”
- NHBC Standards Chapter 4.2, January 2024.
- Google Earth
- British Geological Survey Website & iGeology App

Appendix B Field Work

Appendix B.1 Engineers Logs



Borehole Log

BH1

Sheet 1 of 2

Hole Type BH	Easting	Northing	Ground Level (m) 15.00	Scale 1:50
Project Name St Patricks	Project No. 22440		Start Date 2026-06-02	End Date 2026-06-02

Client	Consultant AN	Contractor
--------	------------------	------------

Inst/ Backfill	Water Levels	Samples and Tests		Level (m)	Depth (m)	Strata	
		Depth (m)	Type/ Ref			Legend	Description
		1.20	SPT		(0.30) 0.30		Yellowish brown sandy gravelly SILT. Gravel is sub angular to sub rounded fine to coarse flint and occasional brick [Made Ground]
					(2.05)		Firm brown silty CLAY. Frequent rootlets. [River Terrace Deposits]
		2.10	SPT		12.90 2.10		Soft to firm yellowish brown gravelly very sandy CLAY. Gravel is angular to subrounded fine to coarse flint. [River Terrace Deposits]
					12.40 2.60		Brown sandy very clayey angular to rounded fine to coarse GRAVEL of flint. [River Terrace Deposits]
		3.00	SPT		(1.10)		Firm brown and orangish brown mottled slightly gravelly sandy CLAY. Occasional rootlets. [River Terrace Deposits]
		4.00	SPT		11.30 3.70		Stiff to very stiff dark Grey CLAY. [London Clay Formation]
					11.00 4.00		
		5.00	SPT				
		6.50	SPT		(11.00)		
		8.00	SPT				
		9.50	SPT				

Continued on next page

Remarks Live rootlets observed to 4.00m bgl	Method, Plant, Stability, Dimensions 0.00 - 15.00m	Logger
Status: FINAL		



Borehole Log


BH1

Sheet 2 of 2

Hole Type BH	Easting	Northing	Ground Level (m) 15.00	Scale 1:50
Project Name St Patricks	Project No. 22440		Start Date 2026-06-02	End Date 2026-06-02

Client	Consultant AN	Contractor
--------	------------------	------------

Inst/ Backfill	Water Levels	Samples and Tests			Level (m)	Depth (m)	Strata	
		Depth (m)	Type/ Ref	Results			Legend	Description
		11.00	SPT	N=31 (5,5/6,7,8,8)				As previous page.
		12.50	SPT	N=27 (4,5/6,6,7,8)				
		14.50	SPT	N=30 (5,5/6,7,8,9)				
					0.00	15.00		End of Borehole at 15.00m



Remarks Live rootlets observed to 4.00m bgl	Method, Plant, Stability, Dimensions 0.00 - 15.00m	Logger
Status: FINAL		



Borehole Log

BH1

SUPPLEMENTARY INFO

Hole Type BH	Easting	Northing	Ground Level (m) 15.00	Scale 1:50
Project Name St Patricks	Project No. 22440		Start Date 2026-06-02	End Date 2026-06-02
Client	Consultant AN	Contractor		

Water Strike - General

Struck (m)	Seal Depth (m)	Casing Depth (m)	Date and Time	Remarks
				No groundwater encountered

SPT - Details

Top Depth (m) (Type)	Casing Depth (m)	Water Depth (m)	Hammer Serial No.	Energy Ratio (%)	Results
1.20 (S)		Dry		67	N=8 (1,1/2,2,2,2)
2.10 (S)		Dry		67	N=44 (1,1/3,4,25,12)
3.00 (S)		Dry		67	N=38 (4,5/8,10,10,10)
4.00 (S)		Dry		67	N=10 (1,2/2,2,3,3)
5.00 (S)		Dry		67	N=11 (1,1/2,3,3,3)
6.50 (S)		Dry		67	N=16 (2,2/3,4,4,5)
8.00 (S)		Dry		67	N=18 (3,3/4,4,5,5)
9.50 (S)		Dry		67	N=23 (3,4/5,6,6,6)
11.00 (S)		Dry		67	N=31 (5,56/7,8,8,8)
12.50 (S)		Dry		67	N=27 (4,5/6,6,7,8)
14.50 (S)		Dry		67	N=30 (5,5/6,7,8,9)

Remarks Live rootlets observed to 4.00m bgl	Method, Plant, Stability, Dimensions 0.00 - 15.00m	Logger
--	---	--------

Status: FINAL





Trial Pit

TPSK1
SUPPLEMENTARY INFO

Hole Type TP	Easting	Northing	Ground Level (m) 1.00	Scale 1:25
-----------------	---------	----------	--------------------------	---------------

Project Name St Patricks	Project No. 22440	Start Date 2026-06-01	End Date 2026-06-01
-----------------------------	----------------------	--------------------------	------------------------

Client	Consultant AN	Contractor
--------	------------------	------------

Water Strike - General

Struck (m)	Seal Depth (m)	Casing Depth (m)	Date and Time	Remarks
				No groundwater encountered

Remarks	Method, Plant, Stability, Dimensions	Logger
---------	--------------------------------------	--------

Status: FINAL



Trial Pit

TPSK2

Sheet 1 of 1

Hole Type TP	Easting	Northing	Ground Level (m) 2.05	Scale 1:25
Project Name St Patricks	Project No. 22440		Start Date 2028-06-01	End Date 2028-06-01

Client	Consultant AN	Contractor
--------	------------------	------------

Inst/ Backfill	Water Levels	Samples and Tests			Level (m)	Depth (m)	Strata	
		Depth (m)	Type/ Ref	Results			Legend	Description
					1.70	0.35		Yellowish brown sandy gravelly SILT. Gravel is sub angular to sub rounded fine to coarse flint and occasional brick [Made Ground]
								Soft to firm orangish brown sandy gravelly CLAY. Gravel is sub angular to sub rounded fine to coarse flint. frequent rootlets to roughly 1.1m [River Terrace Deposits]
					0.35	1.70		Soft to firm yellowish brown and orangish-brown mottled slightly gravelly sandy CLAY. Gravel is subangular to subrounded fine to coarse flint [River Terrace Deposits]
					0.00	2.05	End of Trial Pit at 2.05m	

Remarks	Method, Plant, Stability, Dimensions	Logger
Status: FINAL		



Trial Pit

TPSK2
SUPPLEMENTARY INFO

Hole Type TP	Easting	Northing	Ground Level (m) 2.05	Scale 1:25
Project Name St Patricks	Project No. 22440		Start Date 2026-06-01	End Date 2026-06-01

Client	Consultant AN	Contractor
--------	------------------	------------

Water Strike - General

Struck (m)	Seal Depth (m)	Casing Depth (m)	Date and Time	Remarks
				No groundwater encountered

Remarks	Method, Plant, Stability, Dimensions	Logger
---------	--------------------------------------	--------

Status: FINAL

	Trial Pit				TP3	
					SUPPLEMENTARY INFO	
	Hole Type TP	Easting	Northing	Ground Level (m) 2.00	Scale 1:25	
	Project Name St Patricks		Project No. 22440	Start Date 2026-06-01	End Date 2026-06-01	
Client		Consultant AN		Contractor		
Water Strike - General						
Struck (m)	Seal Depth (m)	Casing Depth (m)	Date and Time	Remarks		
				No groundwater encountered		
Remarks				Method, Plant, Stability, Dimensions		
				Logger		
Status: FINAL						

Appendix C Geotechnical In-Situ and Laboratory Testing**Appendix C.1 Interpretation****Table C.1.1 Interpretation of SPT Tests**

BH	Strata	SPT N60 Blow Counts	Inferred Cohesive Strength
BH1	RTD 0.05-4.00 Gravelly silty CLAY	9-49	Medium to Very High ($C_u = 45-245\text{kPa}$)
	LCF 4.00-15.00 CLAY	11-35	Medium to high ($C_u = 55 - 155\text{kPa}$)

Appendix C.2 Geotechnical In-Situ and Laboratory Results



Laboratory Report



Contract Number: 87438

Client Ref: **22440**
Client PO: **22440/AN**

Date Received: **18-06-2026**
Date Completed: **06-07-2026**
Report Date: **06-07-2026**

Client: **Soils Limited**

This report has been checked and approved by:

Contract Title: **St Patricks Close**
For the attention of: **Akshay Nair**

Shaun Jones
Laboratory manager


Description	Qty
Determination of water content BS EN ISO 17892-1:2014 - * UKAS	5
1 point Liquid & Plastic Limit.. BS EN ISO 17892-12 - * UKAS	5

Notes: Observations and Interpretations are outside the UKAS Accreditation
* - denotes test included in laboratory scope of accreditation
- denotes test carried out by approved contractor
@ - denotes non accredited tests

This certificate is issued in accordance with the accreditation requirements of the United Kingdom Accreditation Service. The results reported herein relate only to the material supplied to the laboratory. This test report/certificate shall not be reproduced except in full, without the approval of GEO Site & Testing Services Ltd. Any opinions or interpretations stated - within this report/certificate are excluded from the laboratories UKAS accreditation.

Approved Signatories:

Brendan Evans (Business Support Co-ordinator) - Darren Bourne (Quality Senior Technician) - Jason Jenkins (Business Development Manager)
Luke Williams (Senior Laboratory Technician) - Paul Evans (Director) - Richard John (Quality/Technical Manager)
Shaun Jones (Laboratory manager) - Shaun Thomas (Site Manager) - Wayne Honey (HR & HSE Manager)

[illegible]

Certificate of Analysis

Certificate Number 26-14955

Issued: 03-Jul-26

Client Soils Limited
Telford House
Sun Valley Business Park
Winnall Close
Winchester
SO23 0LB

Our Reference 26-14955

Client Reference ~ (not supplied)

Order No ~ 22440/AN

Contract Title ~ St Patrick's Church

Description 3 Soil samples.

Date Received 19-Jun-26

Date Started 19-Jun-26

Date Completed 03-Jul-26

Test Procedures Identified by prefix DETSn (details on request).

Notes Opinions and interpretations are outside the laboratory's scope of ISO 17025 accreditation. This certificate is issued in accordance with the accreditation requirements of the United Kingdom Accreditation Service. The results reported herein relate only to the material supplied to the laboratory. This certificate shall not be reproduced except in full, without the prior written approval of the laboratory.

Approved By



Louise Cook
Contracts Manager



2139

Sample Deviations present. See Deviation Table Section for details.

Summary of Chemical Analysis Soil Samples

Our Ref 26-14955

Client Ref ~

Contract Title ~ St Patrick's Church

Lab No	2705425	2705426	2705427
Sample ID ~	TPSK2	BH1	BH1
Depth ~	1.50	3.00	6.00
Other ID ~			
Sample Type ~	SOIL	SOIL	SOIL
Sampling Date ~	n/s	n/s	n/s
Sampling Time ~	n/s	n/s	n/s

Test	Method	LOD	Units			
Metals						
Magnesium Aqueous Extract (2:1)	DETSC 2076*	10	mg/l	12	< 10	17
Inorganics						
pH	DETSC 2008#		pH	8.2	8.4	8.3
Ammoniacal Nitrogen as NH ₄	DETSC 2119*	0.5	mg/kg	0.91	< 0.50	4.3
Chloride Aqueous Extract (2:1)	DETSC 2055	1	mg/l	10	7.1	8.7
Nitrite as NO ₂	DETSC 2055	1	mg/kg	< 1.0	< 1.0	< 1.0
Sulphate Aqueous Extract as SO ₄ (2:1)	DETSC 2076#	10	mg/l	150	50	340
Sulphur as S, Total	DETSC 2320	0.01	%	0.01	< 0.01	0.30
Sulphate as SO ₄ , Total	DETSC 2321#	100	mg/kg	246	186	2110

Information in Support of the Analytical Results

Our Ref 26-14955

Client Ref ~

Contract ~ St Patrick's Church

Containers Received & Deviating Samples

Lab No	Sample ID ~	Date Sampled ~	Containers Received	Holding time exceeded for tests	Incorrect container for tests
2705425	TPSK2 1.50 SOIL		PT 1L	Sample date and/or time not supplied, Anions 2:1 (30 days), Ammonia (3 days), Total Sulphur ICP (7 days), Total Sulphate ICP (30 days), Metals ICP Prep (182 days), Ammoniacal Nitrogen as NH ₄ (365 days), pH + Conductivity (7 days)	
2705426	BH1 3.00 SOIL		PT 1L	Sample date and/or time not supplied, Anions 2:1 (30 days), Ammonia (3 days), Total Sulphur ICP (7 days), Total Sulphate ICP (30 days), Metals ICP Prep (182 days), Ammoniacal Nitrogen as NH ₄ (365 days), pH + Conductivity (7 days)	
2705427	BH1 6.00 SOIL		PT 1L	Sample date and/or time not supplied, Anions 2:1 (30 days), Ammonia (3 days), Total Sulphur ICP (7 days), Total Sulphate ICP (30 days), Metals ICP Prep (182 days), Ammoniacal Nitrogen as NH ₄ (365 days), pH + Conductivity (7 days)	

Key: P-Plastic T-Tub

Normec DETS cannot be held responsible for the integrity of samples received whereby the laboratory did not undertake the sampling. In this instance samples received may be deviating. Deviating Sample criteria are based on British and International standards and laboratory trials in conjunction with the UKAS note 'Guidance on Deviating Samples'. All samples received are listed above. However, those samples that have additional comments in relation to hold time, inappropriate containers etc are deviating due to the reasons stated. This means that the analysis is accredited where applicable, but results may be compromised due to sample deviations. If no sampled date (soils) or date+time (waters) has been supplied then samples are deviating. However, if you are able to supply a sampled date (and time for waters) this will prevent samples being reported as deviating where specific hold times are not exceeded and where the container supplied is suitable.

Soil Analysis Notes

Inorganic soil analysis was carried out on a dried sample, crushed to pass a 250µm sieve

Organic soil analysis was carried out on an 'as received' sample. Organics results are corrected for moisture and expressed on a dry weight basis.

The Loss on Drying, used to express organics analysis on an air dried basis, is carried out at a temperature of 28°C +/- 2°C.

Disposal



From the issue date of this test certificate, samples will be held for the following times prior to disposal :-

Soils - 1 month, Liquids - 2 weeks, Asbestos (test portion) - 6 months

Appendix D Preliminary Pile Design

Preliminary Pile Working Loads
Single Vertically Loaded Pile (kN)

Name:	St.Patrick's C	N _c value	9	Pile Start Depth:	3	FOS
Job No:	22440	α value:	0.45	Pile Final Depth:	15	Shaft
Date:	2.7.26			Pile Increment:	1	Base



Pile Diameter (m):

Pile Depths (m bgl)	0.30	0.45	0.60
	Shaft	Base	Total
3.0			
4.0	5	10	15
5.0	15	20	35
6.0	25	30	55
7.0	40	45	85
8.0	55	60	115
9.0	70	75	145
10.0	90	100	190
11.0	110	130	240
12.0	130	160	290
13.0	150	190	340
14.0	175	225	400
15.0	200	295	495

Appendix E Information Provided by the Client



Schedule of Accommodation:

Bungalow 1.	3 bedroom	GIA 128m ²
Bungalow 2.	3 bedroom	GIA 118m ²

Note:
Drawing to be read in conjunction with:
Proposed Site Plan
Tree Report
BGN Report
Flood Risk Assessment

DRAWING REFERENCE	REVISION	SCALE
608 PL03	C	@A3

PROJECT:
Land to East of St Patricks RC Church, Manor Road

DRAWING:
SITE PLAN: PROPOSED

732, southwood road, hollying island, hampshire PO11 9GQ
01752 460974 01734 894873 niall@lilleyarchitecture.com

Soils Limited
Geotechnical & Environmental Consultants

**Telford House,
Unit 11 Sun Valley Business Park,
Winnall Close,
Winchester,
England SO23 0LB**

**T: 01962 673 330
W: soilslimited.co.uk**


Appendix G

Southern Water Sewer Records

Appendix H

Site & Proposed Impermeable Areas


Footprint of buildings 246m²



Appendix I


Foul & Surface Water Drainage Layout

Foul & Surface Water Drainage Layout



Appendix J

Surface Water Drainage Calculations



MasterDrain
HY 11.0

HAMILL DAVIES LIMITED

Consulting Civil & Structural Engineers
Ivydale, Lower Chase Road, Swanmore,
Hampshire, SO32 2PB
Tel: 01489 893 596 Fax: 01489 890 715
brian.w.hamill@btopenworld.com

Job No.	26/4613		
Sheet no.	1		
Date	17/08/26		
By	B.H.	Checked	Reviewed

Project Land to the east of St. Patrick's Church, Hayling Island

Title BREEAM SUR1 calculations for PORTSMOUTH

Data:-

Hydrology (FSR):-

Location = PORTSMOUTH
Long reference = 465101
M5-60 (mm) = 18
r = 0.35
Hyd. area = 7
Hydrograph = Summer

WRAP = 3
Grid reference = SU6501
SAAR (mm/yr) = 710
Soil = 0.37
Hyd. zone = 4
Area = England & Wales ✓

Site values used in design:-

Total site area = 0.1121 ha Climate change factor = 45%
Pre-dev area drained = 0.0000 ha Post-dev area drained = 0.0516 ha
Imperm runoff factor = 98% Perm runoff factor = 20%

Pre-development

Area to soakaways = 0.0000 ha Area to other SUDS = 0.0000 ha
Perv. area to SUDS = 0.0000 ha Pre-dev flow to drain = 0.00 l/s

Post-development

Area to soakaways = 0.0000 ha Area to other SUDS = 0.0000 ha
Perv. area to SUDS = 0.0000 ha Post-dev flow to drain = 0.70 l/s

Calculations:-

Revised Post-dev Imperm. area = 0.052 ha
Equiv. Post-dev Imperm. area = 0.051 ha
Equiv. Post-dev Perm. area = 0.012 ha
Total Pre-dev equiv. area ha = 0.022 ha
Total Post-dev equiv. area ha = 0.063 ha
100 yr 6 hour mean intensity = 10.03mm/hr

Results:-

Pre-dev peakflow runoff (l/s) (m³/s)

R.P.	15	30	60	120	240	360	480	600	Max	CCF	Final	R.P.
1	6.6	4.3	2.8	1.8	1.1	0.9	0.7	0.6	6.6	N/A	6.6	1
30	15.9	10.6	6.8	4.2	2.5	1.9	1.5	1.3	15.9	N/A	15.9	30
100	20.5	13.8	8.9	5.5	3.3	2.4	2.0	1.7	20.5	N/A	20.5	100

Post-dev peakflow runoff (l/s)

R.P.	15	30	60	120	240	360	480	600	Max	CCF	Final	R.P.
1	18.4	12.1	7.9	5.0	3.2	2.4	2.0	1.7	18.4	45	26.7	1
30	44.4	29.5	18.9	11.7	7.1	5.3	4.3	3.6	44.4	45	64.3	30
100	57.2	38.5	24.8	15.4	9.3	6.8	5.5	4.6	57.2	45	83.0	100

100 year 6 hour (x Climate Change Factor) storm gives:-

Pre-dev runoff volume m³ = 13.5m³
Post-dev rainfall volume = 54.7m³
Post-dev volume m³ (excess above SUDS) = 54.7m³
100 yr 6 hour mean intensity = 10.03mm/hr
Pre-dev volume to drain at 0 l/s = 0.0 m³
Post-dev volume to drain at .7 l/s = 15.4 m³
→ Post-dev storage volume = 39.3m³ ←
Post-dev 5mm imperm volume = 2.6 m³
Post-dev 5mm perm volume = 3.0 m³

$Q_{BAR(rural)} = 0.327 \text{ l/s}$ or 2.921 l/s/ha or 0.000 cumecs - from IoH 124.

The rainfall rates are calculated using the location specific values above in accordance with the Wallingford procedure.

Appendix I

Flood & Water Management Template

1	Background information on the proposed design. Including proposal; site; plans of surface water drainage and any SuDS featured in the scheme
2	Evidence that the applicant understands the sensitivity of discharge points relating to the receiving water body. Where this is main river or discharging through contaminated land the LPA may have to consult the Environment Agency (EA)
3	Evidence of and information on the existing surface water flow paths of undeveloped (greenfield) sites
4	Evidence of and information on the existing drainage network for previously developed (brownfield) sites
5	Identification of and information on areas that may have been affected by failures in the existing drainage regime
6	Evidence that the proposed drainage will follow the same pattern as the existing. This avoids directing flow to other locations.
7	Information evidencing that the correct level of water treatment exists in the system in accordance with the Ciria SuDS Manual C753
8	<i>Where infiltration is used for drainage</i> , evidence that a suitable number of infiltration tests have been completed. These need to be across the whole site; within different geologies and to a similar depth to the proposed infiltration devices. Tests must be completed according to the BRE 365 method or another recognised method including British Standard BS 5930: 2015
9	<i>If not using infiltration for drainage</i> - Existing and proposed run-off rate calculations completed according to a suitable method such as IH124 or FEH. Information is available from UK Sustainable Drainage: Guidance and Tools. Calculations must show that the proposed run off rates do not exceed the existing run-off rates. This must be shown for a one in one year event plus climate change and a one in one hundred year event plus climate change.
10	<i>If not using infiltration for drainage</i> - Existing and proposed run-off volume calculations completed according to a suitable method such as IH124 or FEH. Calculations must show that, where reasonably practical, runoff volume should not exceed the greenfield runoff volume for the same event. This must be shown for a 1 in 100 year, 6 hour rainfall event
11	Evidence that enough storage/attenuation has been provided without increasing the runoff rate or volume. This must be shown for a 1 in 100 year plus climate change event
12	Evidence that runoff exceeding design criteria has been considered. Calculations and exceedance flow diagram/plans must show where above ground flooding might occur and where this would pool and flow.
13	Maintenance regimes of entire surface water drainage system including individual SuDS features, including a plan illustrating the organisation responsible for each element. Evidence that those responsible/adopting bodies are in discussion with the developer. For larger/phased sites, we need to see evidence of measures taken to protect and ensure continued operation of drainage features during construction.
14	Evidence that Urban Creep has been considered in the application and that a 10% increase in impermeable area has been used in calculations to account for this.