REFRESH TAXI ROAD MARKING LIKE FOR LIKE

TAXIS ONLY

PS1
'FOOTWAY / CYCLEWAY SHARED USE'
DIAG 956

PS1 & 2

CYCLISTS DISMOUNT

PS2
'CYCLISTS DISMOUNT'
DIAG 966

SIGNS TO BE MOUNTED BACK TO BACK ON NEW POST 1.8m HIGH MIN 500mm FROM FACE OF EXISTING WALL

CYCLE CROSS HATCHING TO BE REFRESHED LIKE FOR LIKE

CYCLE SYMBOL DIAG 1057 TO BE REFRESHED LIKE FOR LIKE

NEW LINING TIES INTO EXISTING (TO BE REFRESHED)

2.6m EXISTING DIMENSION

1018.1 (75)

1017 (75)

EXISTING SINGLE YELLOW MARKING TO BE REFRESHED. DIMENSIONS SHOWN FOR CLARITY.

2.6m EXISTING DIMENSION

WHITE ROAD MARKINGS ON EXISTING CROSSING TO BE REFRESHED

1017 (75)

REFRESH TAXI ROAD MARKING LIKE FOR LIKE

TAXIS ONLY

1018.1 (75)

NOTES

1. DO NOT SCALE FROM THIS DRAWING
2. ALL DIMENSIONS IN METRES UNLESS OTHERWISE STATED
3. PARTS OF THIS DRAWING SHOULD BE SHOWN IN **COLOUR**. IF THIS NOTE IS NOT **RED** REPRINT A COLOURED COPY.
4. .FOR GROUND INVESTIGATION REPORT REFER TO TF-24-356-R01 GIR @ Havant Train Station (Final) Report reference GIR (Final) PRODUCED BY TERRA FIRMA.
5. FOR HIGHWAY BOUNDARY AND LAND OWNERSHIP DETAILS REFER TO HCC DRAWING REFERENCE CJ009595-HES-SGN- FB1051-DR-S-1708 Rev S4 P01
6. EXISTING LAMP COLUMN TO BE RELOCATED BY STREET LIGHTING CONTRACTOR
7. REFRESHED LINING STATED ON THE DRAWING IS TO BE LIKE FOR LIKE.
8. REFER TO SIGNS AND LINES SCHEDULE FOR MORE DETAILS
9. ALL ROAD MARKINGS ARE TO COMPLY WITH THE TRAFFIC SIGNS REGULATIONS AND GENERAL DIRECTIONS 2016.
10. ALL ROAD MARKINGS SHALL BE YELLOW THERMOPLASTIC SCREED WITH SURFACE APPLIED SOLID GLASS BEADS
11. 1017 (75) PROPOSED SINGLE YELLOW LINE
12. 1018.1 (2x75) PROPOSED DOUBLE YELLOW NO WAITING AT ANY TIME LINE

KEY

PS	PROPOSED SIGN AND POST
1018.1 (75)	PROPOSED DOUBLE YELLOW 'NO WAITING AT ANY TIME ROAD MARKING WITH DIAGRAM NUMBER AND WIDTH IN MILLIMETRES INDICATED IN BRACKETS
1017 (75)	PROPOSED SINGLE YELLOW NO WAITING RESTRICTION LINE WITH DIAGRAM NUMBER AND WIDTH IN MILLIMETRES INDICATED IN BRACKETS
	RED LINE APPLICATION BOUNDARY

0 5 10 20 30 40 50 100

DRAFT

© CROWN COPYRIGHT AND DATABASE RIGHTS 2026
ORDNANCE SURVEY 100019180

SUIT	REV	WORK IN PROGRESS ISSUE AND DESCRIPTION OF AMENDMENTS	DATE	DESIGNER	CAD	CHKD	APPD
D1	P05	FOR COSTING	17.07.2026	GF	ADS		
D1	P04	FOR COSTING	10.07.2026	GF	ADS		
S2	P03	DRAFT FOR DISCUSSION / PRELIMINARY ESTIMATES	07.07.2026	GF	ADS		
S2	P02	DRAFT FOR DISCUSSION / PRELIMINARY ESTIMATES	03.07.2026	GF	ADS		
S2	P01	DRAFT ISSUE TO CLIENT	25.06.2026	GF	ADS		

CLIENT
HAMPSHIRE COUNTY COUNCIL
UNIVERSAL SERVICES DIRECTORATE
STRUCTURES

CONSULTANT
Hampshire County Council
Engineering Services
TIM LAWTON BEng CEng FICE FCIHT : ASSISTANT DIRECTOR OF UNIVERSAL SERVICES

HORIZONTAL SCALE @ A1: 1:100
VERTICAL SCALE @ A1: N/A
SHEET NUMBER: 1 OF 1

SCHEME: HAVANT FOOTBRIDGE REPLACEMENT
JOB No. C.J009595.01

DRAWING TITLE: TRAFFIC SIGN AND ROAD MARKINGS SOUTHERN SECTION
HCC CAD PLOT: 17/7/2026 11:20:23

CJ009595-HEH-HMS- FB1051 -DR-CD-0003

SUIT D1 REV P05

HCC CAD FILE: K:\Eng\Roads\Schemes\CJ009595 Havant Footbridge\Drainage\03-Drawings\02-General\detailed design\C.J009595-HEH-HMS-FB1051-DR-CD-0003 southern Signs and Road Markings.dwg

STATUS OF DRAWING AT SUITABILITY - RED BACKGROUND = WORK IN PROGRESS, AMBER BACKGROUND = SHARED NON-CONTRACTUAL, GREEN BACKGROUND = EARLY PUBLISH & PUBLISHED CONTRACTUAL