

Originating Office



1st Floor

36 Bennetts Hill

Birmingham

B2 5SN

Project Number	LP2412
Project Name	Havant Thicket Reservoir Visitor Centre
Project Area	Future Water

Specification Title	Discipline	Document	Clause No.	Ref	Rev	Q31
TREE SCHEDULE - Semi-Mature	LA			Q31	P04	
	Document Status		PLANNING			

Filename	S:\LP2412\Project admin\07.0 Pre-tender\7.1 Landscape specifications & plant schedules\Live\[19104-FIR-01x459-XX-SH-LP-007002.xlsx]Schedule	Author	Checked Date	Initials	Authorised Date	Initials
		TL	29.05.26	JP	29.05.26	JP

Revisions			QA System Checks				
Rev	Date	Description/Details	Author	Checked Date	Initials	Authorised Date	Initials
P01	27.04.26	Issued for Planning.	TL	27.04.26	JP	27.04.26	JP
P02	29.05.26	Amendments reflecting planting plan updates.	TL	29.05.26	JP	29.05.26	JP
P03	24.07.26	Issued for Pre-Commencement Planning.	AS	24.07.26	JP	24.07.26	JP
P04	19.08.26	Issued for Pre-Commencement Planning.	AS	19.08.26	JP	19.08.26	JP

fira landscape architecture & urban design				1st Floor, 36 Bennetts Hill, Birmingham, B2 5SN			
Job No.:	Project Name	Issue Status	Author	Checked	Date	Revision	Filename
LP2412	Havant Thicket Reservoir Visitor Centre	PLANNING	TL	JP	29.05.26	P04	S:\LP2412\Project admin\07.0 Pre-tender\7.1 Landscape specifications & plant schedules\Live\[19104-FIR-01x459-XX-SH-LP-007002.xlsx]Schedule
	Future Water						
ABBREVIATIONS USED IN THE SCHEDULE:		T= Transplant, W= Whip, F= Feathered, HS= Half Standard, S= Standard, SS= Select Standard, HS= Heavy Standard, EHS= Extra Heavy Standard, SM= Semi Mature, MS= Multi-Stemmed, O= Open Ground, W= Root Wrapped, WRB= Wire Rootball					
Notes:		Trees should only be planted during the appropriate Season between late October and late March. Trees should NOT be planted 'out of season' unless agreed with the Landscape Architect. Trees should only be Planted while soil and weather conditions are suitable and NOT during periods of frost or strong winds					
TREE SCHEDULE - Semi-Mature							
Species	Girth and Height (cm)	Times Transplanted	Clear Stem (CS) or Feathered (F)	Classification	Notes	Quantity No.	Rate
Acer campestre	20-25	4x	CS	SM/WRB	Avenue matching crown height shape and clear stem.	49	
Alnus glutinosa	20-25	4x	CS	SM/WRB	Avenue matching crown height shape and clear stem.	16	
Betula pendula	20-25	4x	CS	SM/WRB	Avenue matching crown height shape and clear stem.	33	
Betula pubescens	20-25	4x	CS	SM/WRB	Avenue matching crown height shape and clear stem.	14	
Carpinus betulus	20-25	4x	CS	SM/WRB	Avenue matching crown height shape and clear stem.	17	
Carpinus betulus 'Fastigiata'	20-25	4x	CS	SM/WRB	Avenue matching crown height shape and clear stem.	13	
Castanea sativa	20-25	4x	CS	SM/WRB	Avenue matching crown height shape and clear stem.	13	
Crataegus monogyna	20-25	4x	CS	SM/WRB	Avenue matching crown height shape and clear stem.	9	

fira landscape architecture & urban design				1st Floor, 36 Bennetts Hill, Birmingham, B2 5SN			
Job No.:	Project Name	Issue Status	Author	Checked	Date	Revision	Filename
LP2412	Havant Thicket Reservoir Visitor Centre	PLANNING	TL	JP	29.05.26	P04	S:\LP2412\Project admin\07.0 Pre-tender\7.1
	Future Water						Landscape specifications & plant schedules\Live\[19104 FIR-01x459-XX-SH-LP-007002.xlsx\Schedule
ABBREVIATIONS USED IN THE SCHEDULE:		T= Transplant, W= Whip, F= Feathered, HS= Half Standard, S= Standard, SS= Select Standard, HS= Heavy Standard, EHS= Extra Heavy Standard, SM= Semi Mature, MS= Multi-Stemmed, O= Open Ground, W= Root Wrapped, WRB= Wire Rootball					
Notes:		Trees should only be planted during the appropriate Season between late October and late March. Trees should NOT be planted 'out of season' unless agreed with the Landscape Architect. Trees should only be Planted while soil and weather conditions are suitable and NOT during periods of frost or strong winds					
TREE SCHEDULE - Semi-Mature							
Species	Girth and Height (cm)	Times Transplanted	Clear Stem (CS) or Feathered (F)	Classification	Notes	Quantity No.	Rate
Prunus avium	20-25	4x	CS	SM/WRB	Avenue matching crown height shape and clear stem.	26	
Quercus robur	20-25	4x	CS	SM/WRB	Avenue matching crown height shape and clear stem.	18	
Sorbus aria	20-25	4x	CS	SM/WRB	Avenue matching crown height shape and clear stem.	6	
Tilia cordata	20-25	4x	CS	SM/WRB	Avenue matching crown height shape and clear stem.	58	