



B2 5SN

Project Number	LP2412
Project Name	Havant Thicket Reservoir Visitor Centre
Project Area	Future Water

Specification Title	Discipline	Document	Clause No.	Ref	Rev	Q31
TREE SCHEDULE - Nursery Stock	LA			Q31	P04	
	Document Status		PLANNING			

Filename	S:\LP2412\Project admin\07.0 Pre-tender\7.1 Landscape specifications & plant schedules\Live\19104-FIR-01x459-XX-SH-LP-007001.xlsx\Cover Sheet	Author	Checked Date	Initials	Authorised Date	Initials
		TL	29.05.26	JP	29.05.26	JP

[illegible]

fira landscape architecture & urban design				1st Floor, 36 Bennetts Hill, Birmingham, B2 5SN			
Job No.:	Project Name	Issue Status	Author	Checked	Date	Revision	Filename
LP2412	Havant Thicket Reservoir Visitor Centre	PLANNING	TL	JP	29.05.26	P04	S:\LP2412\Project admin\07.0 Pre-tender\7.1
	Future Water						Landscape specifications & plant
							schedules\Live\19104-FIR-01x459-XX-SH-LP.
ABBREVIATIONS USED IN THE SCHEDULE:		T= Transplant, W= Whip, F= Feathered, HS= Half Standard, S= Standard, SS= Select Standard, HS= Heavy Standard, EHS= Extra Heavy Standard, SM= Semi Mature, MS= Multi-Stemmed, O= Open Ground, W= Root Wrapped, WRB= Wire Rootball					
Notes:		Trees should only be planted during the appropriate Season between late October and late March. Trees should NOT be planted 'out of season' unless agreed with the Landscape Architect. Trees should only be Planted while soil and weather conditions are suitable and NOT during perios of frost or strong winds					
TREE SCHEDULE - Nursery Stock							
Species	Girth and Height (cm)	Times Transplanted	Clear Stem (CS) or Feathered (F)	Classification	Notes	Quantity No.	Rate
Acer campestre	175-200	2x		WRB	Fully furnished to base	20	
Acer campestre (T)	60-90	1+1		T/O	Minimum of 3 breaks	473	
Alnus glutinosa	175-200	2x		WRB	Fully furnished to base	1	
Alnus glutinosa (T)	60-90	1+1		T/O	Minimum of 3 breaks	473	
Betula pubescens (T)	60-90	1+1		T/O	Feathered from pot level	473	
Betula pubescens	175-200	2x		WRB	Fully furnished to base	13	
Carpinus betulus	175-200	2x		WRB	Fully furnished to base	10	
Castanea sativa	175-200	2x		WRB	Fully furnished to base	14	

fira landscape architecture & urban design				1st Floor, 36 Bennetts Hill, Birmingham, B2 5SN			
Job No.:	Project Name	Issue Status	Author	Checked	Date	Revision	Filename
LP2412	Havant Thicket Reservoir Visitor Centre	PLANNING	TL	JP	29.05.26	P04	S:\LP2412\Project admin\07.0 Pre-tender\7.1 Landscape specifications & plant schedules\Live\19104-FIR-01x459-XX-SH-LP.
	Future Water						
ABBREVIATIONS USED IN THE SCHEDULE:		T= Transplant, W= Whip, F= Feathered, HS= Half Standard, S= Standard, SS= Select Standard, HS= Heavy Standard, EHS= Extra Heavy Standard, SM= Semi Mature, MS= Multi-Stemmed, O= Open Ground, W= Root Wrapped, WRB= Wire Rootball					
Notes:		Trees should only be planted during the appropriate Season between late October and late March. Trees should NOT be planted 'out of season' unless agreed with the Landscape Architect. Trees should only be Planted while soil and weather conditions are suitable and NOT during perios of frost or strong winds					
TREE SCHEDULE - Nursery Stock							
Species	Girth and Height (cm)	Times Transplanted	Clear Stem (CS) or Feathered (F)	Classification	Notes	Quantity No.	Rate
Corylus avellana (T)	60-90	1+1		T/O	Minimum of 3 breaks	473	
Crataegus monogyna (T)	60-90	1+1		T/O	Minimum of 3 breaks	625	
Ilex aquifolium (T)	60-90	1+1		T/O	Minimum of 3 breaks	316	
Quercus robur (T)	60-90	1+1		T/O	Minimum of 3 breaks	316	
Quercus robur	175-200	2x		WRB	Fully furnished to base	12	
Tilia cordata	175-200	2x		WRB	Fully furnished to base	14	
NATIVE HEDGE MIX							
Corylus avellana (T)	40-60	1+1		T/O	0.45Ctr Double Staggered at 0.3m offset	79	

fira landscape architecture & urban design				1st Floor, 36 Bennetts Hill, Birmingham, B2 5SN				
Job No.:	Project Name	Issue Status	Author	Checked	Date	Revision	Filename	
LP2412	Havant Thicket Reservoir Visitor Centre	PLANNING	TL	JP	29.05.26	P04	S:\LP2412\Project admin\07.0 Pre-tender\7.1	
	Future Water						Landscape specifications & plant schedules\Live\[19104-FIR-01x459-XX-SH-LP.	
ABBREVIATIONS USED IN THE SCHEDULE:		T= Transplant, W= Whip, F= Feathered, HS= Half Standard, S= Standard, SS= Select Standard, HS= Heavy Standard, EHS= Extra Heavy Standard, SM= Semi Mature, MS= Multi-Stemmed, O= Open Ground, W= Root Wrapped, WRB= Wire Rootball						
Notes:		Trees should only be planted during the appropriate Season between late October and late March. Trees should NOT be planted 'out of season' unless agreed with the Landscape Architect. Trees should only be Planted while soil and weather conditions are suitable and NOT during perios of frost or strong winds						
TREE SCHEDULE - Nursery Stock								
Species		Girth and Height (cm)	Times Transplanted	Clear Stem (CS) or Feathered (F)	Classification	Notes	Quantity No.	Rate
Crataegus monogyna (T)		40-60	1+1		T/O	0.45Ctr Double Staggered at 0.3m offset	386	
Ilex aquifolium (T)		40-60	1+1		T/O	0.45Ctr Double Staggered at 0.3m offset	79	
Prunus spinosa (T)		40-60	1+1		T/O	0.45Ctr Double Staggered at 0.3m offset	79	
Rosa canina (T)		40-60	1+1		T/O	0.45Ctr Double Staggered at 0.3m offset	79	
Viburnum opulus (T)		40-60	1+1		T/O	0.45Ctr Double Staggered at 0.3m offset	79	