



- Reserved Matters Boundary
- Buildings
- Grassland & Verges:
150mm of topsoil
450mm of subsoil
- Structural Areas & Mounds:
450mm of topsoil
450mm of subsoil
- Meadow Area:
50mm of topsoil
450mm of subsoil
- Submerged 450mm of subsoil
- Semi Mature Trees
2100mm x 2100mm pits
- Advanced Nursery Tree Stock
1200mm x 1200mm pits
- Woodland planting
- Existing retained trees

Do not scale this drawing. All dimensions to be verified on site.
Drawings are to be read in conjunction with all related architectural and engineering drawings, details and all other relevant information.
Any discrepancies between this drawing and any other information should be reported to the landscape architect.
Copyright © Fira Landscape Ltd.

Revision | Date | Drawn by | Amendments:
P01 | 24.07.26 | JP | Pre-commencement planning information.
P02 | 29.07.26 | JP | Pre-commencement planning information.
P03 | 31.07.26 | JP | Pre-commencement planning information.
P04 | 19.08.26 | JP | Pre-commencement planning information.

Notes:
Construction drawing to be read in conjunction with the following:
Refer to Civil Engineer's drawings and specifications for all drainage levels, falls and gradients, highway requirements, sewer and manholes, paving, loading, over-cuts, white lining and setting out of all roads, car parks and vehicular areas.
Refer to M&E Engineer's drawings and specifications for all lighting (including sports pitches where appropriate), CCTV and barrier, culvert and controlled access.
Refer to Structural Engineer's drawings and specifications for all guardrail and barrier loading, vehicular gates and retaining structures.
Refer to Architect's drawings and specifications for fire routes, bin stores, setting out of all buildings including ancillary structures and finished floor levels.
Scape layout and fencing shown in outline. Refer to specialist contractor's details and specification, including setting out and fine marking.
All final service routes in relation to tree locations to be coordinated and appropriate root barriers installed.
Refer to arboricultural advice, details and specifications for the protection of retained trees in relation to construction.
Contractors are to verify all site dimensions and conditions before construction.
This drawing is to be read in conjunction with all other relevant drawings. Main Contractor to be notified of any discrepancies in figured dimensions from site.

Project:
Havant Thicket Reservoir Visitor Centre
Portsmouth Water

Job Number:
LP2412

Drawing Title:
Soil Management Strategy

Portsmouth Water Drawing Number:
HTR-FIR-XX-ZZ-DR-L-0002

Fira Drawing Number:
LP2412-FIR-XX-XX-D-L-0002

Drawing Status:
PLANNING

First Issue Date:
24.07.26

Scale:
1:500@A0

Revision:
P 0 4
Drawn by:
AS
Authorised:
JP

fira

0121 790 1000 | mail@fira-4.com